

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL

Name of the Work / Contract No:

Work of " Providing, fixing, and changing of previously installed phase separators of 125 number span to prevent unwanted short circuit causes due to clapping of conductors on high wind during the rainy season, with changing of damaged insulators, cradleguard wires, and air break switches of 500 kVA transformers installed in three number sidings (Balumath, Bukru & Phulbasiya siding) Chamatu patch and kundi patch under Magadh OCP, M-S Area."

NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/25-26/02; Dated:- 05.04.2025.

Category of Services (To Be Selected by Department)

Category of Bidder (To Be Selected by Bidder)

ITC Available

Works Contract

Bidder's Status (Mandatory)

Total GST(in Rs.)

GST to be Paid By Bidder (in Rs.)

GST to be Paid By CIL/Subsidiary (in Rs.)

Name of the Bidder/ Bidding Firm / Company :

Select

0.00

0.00

0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Supply and fixing of LT PVC SPACER for Four wire System	250	Each		0.00	INR Zero Only
2	Erection of G.I wire no-6/8 SWG including binding etc.as required for cage cradle and crosslacing.	25	span		0.00	INR Zero Only
3	Supply and fixing of Air Break Switch	3	nos		0.00	INR Zero Only
4	Supplying of two lengths of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) double pole cross arm for three wire 11KV over head line conductors complete with through bolts and nuts for clamping to the poles, 50 mm X 6 mm M.S. flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/ fittings, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required.	6	Set		0.00	INR Zero Only
5	40 mm dia. G.I. pipe (medium class)	18	Mtr		0.00	INR Zero Only
6	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required as required for Conductor Tensioning as where required due to sag of conductor (10 span X 50 length X 4 wire X 0.148 kg/Metre)=296 kg	296	Kg		0.00	INR Zero Only
7	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required.	30	Set		0.00	INR Zero Only
8	Erection of angle Iron/channel iron cross arm on 8 wood/RCC/PCC/steel tubular or Rail pole for 4 wire system.	30	Set		0.00	INR Zero Only
9	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc, as required.	50	Set		0.00	INR Zero Only
10	Supplying and erection of 100 mm X 110 mm shackle insulator with G. I. Bolt, nuts and straps etc, as required	25	Set		0.00	INR Zero Only
12	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	