

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority:STAFF OFFICER CIVIL

Name of Work: Cutting of Garland drain, cleaning existing drain and providing hume pipe culvert near WB no. 01 at TSOCP, Hazaribagh Area under Monsoon action plan 25-26

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Item Description/ Heading					
1.01	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be levelled and neatly dressed. All kinds of soil	5527.00	Cum	128.05	707732.35	INR Seven Lakh Seven Thousand Seven Hundred & Thirty Two and Paise Thirty Five Only
1.02	Laying Reinforced Cement Concrete Pipe NP4/prestrssed concrete pipe on first class bedding in single row . (Laying Reinforced cement concrete pipe NP4/prestrssed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets .)1000 mm dia	37.50	m	8910.00	334125.00	INR Three Lakh Thirty Four Thousand One Hundred & Twenty Five Only
1.03	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	11.43	Cum	5916.00	67619.88	INR Sixty Seven Thousand Six Hundred & Nineteen and Paise Eighty Eight Only
1.04	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	120.83	Cum	114.40	13822.95	INR Thirteen Thousand Eight Hundred & Twenty Two and Paise Ninety Five Only

1.05	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	7.05	Cum	5322.15	37521.16	INR Thirty Seven Thousand Five Hundred & Twenty One and Paise Sixteen Only
1.06	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	36.28	Sqm	284.75	10330.73	INR Ten Thousand Three Hundred & Thirty and Paise Seventy Three Only
2.00	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					1171152.07	INR Eleven Lakh Seventy One Thousand One Hundred & Fifty Two and Paise Seven Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					