

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: S.O(Civil), Rajrapa Area

Name of Work :- Cleaning of drains, roof repairing of sheds, tree trimming, and providing RCC drain near store under Rajrapa Washery project for Monsoon Preparation under Rajrapa washery project under Rajrapa Area.

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7
1	Providing corrugated G.S. sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.L. limpet washers or with G.L. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.0.63 mm thick with zinc coating not less than 275gm/ m ²	210.00	Sqm	821.25	172462.50	INR One Lakh Seventy Two Thousand Four Hundred & Sixty Two and Paise Fifty Only
2	Extra for providing and fixing wind ties of 40x 6mm flat iron section.	200.00	m	138.75	27750.00	INR Twenty Seven Thousand Seven Hundred & Fifty Only
3	Pruning trimming shaping of tree/sharubs ht 25 feet and above) including removal of cut material as per direction of office incharge (necessary T&P shall be arranged by the contractor	1000.00	Cum	77.74	77740.00	INR Seventy Seven Thousand Seven Hundred & Forty Only
4	Excavation in soil with Dozer with lead upto 100 meters. Excavation for road way in soil by mechanical means including cutting and pushing the earth to site of embankment upto a distance of 100 meters(average lead 50meters) including trimming bottom and side slope in accordance with requirements of lines grades and cross sections	3477.96	Cum	67.00	233023.32	INR Two Lakh Thirty Three Thousand & Twenty Three and Paise Thirty Two Only
5	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	63.00	Cum	188.45	11872.35	INR Eleven Thousand Eight Hundred & Seventy Two and Paise Thirty Five Only
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:3:6 (1 cement: 3manufactured sand derived from Recycled concrete Aggregate (RCA): 6 graded stone aggregate 20 mm nominal size Recycled Aggregate (RA)	7.00	Cum	4375.95	30631.65	INR Thirty Thousand Six Hundred & Thirty One and Paise Sixty Five Only
7	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	18.48	Cum	7365.50	136114.44	INR One Lakh Thirty Six Thousand One Hundred & Fourteen and Paise Forty Four Only
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level. Thermo-Mechanically Treated bars.	1478.40	Kg	75.85	112136.64	INR One Lakh Twelve Thousand One Hundred & Thirty Six and Paise Sixty Four Only

9	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete.	168.00	Sqm	262.55	44108.40	INR Forty Four Thousand One Hundred & Eight and Paise Forty Only
10	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					845839.30	INR Eight Lakh Forty Five Thousand Eight Hundred & Thirty Nine and Paise Thirty Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only