

ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required. (Above 8.0 mtr and upto 10 mtr)	10.00	Nos.			0.00	INR Zero Only
1.02	Supplying of 50 mm X 8 mm M.S. flat iron pole top bracket/ cross arm for single 11/ 22/33 KV over head line conductor complete with fixing clamps, bolts, nuts and washers drilling holes for insulator pins, bolts and nuts etc and painting with primer and finish paint as required.	10.00	Nos.			0.00	INR Zero Only
1.03	Supplying and erection of galvanised stay set for 11 KV over head lines completewith 19/ 20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X7.5 mm thick, thimble, stay clamps, turn buckle (20 mm X 600 mm), 7/ 4.00 mm diaG.I. stay wire and 11 KV strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	11.00	Nos.			0.00	INR Zero Only
1.04	Erection of pole top/ straight two wire/ V shape two wire, angle iron/ channel iron,cross arm on steel tubular/ rail/ PCC pole for 11/22/33 KV as required.	10.00	Sets			0.00	INR Zero Only
1.05	Supplying of two lengths of channel iron 75mm x 40mm x 6mm (7.14kg per metre) double pole cross arm for three wire 11KV overhead line conductors complete with through bolts and nuts for clamping of the poles, 50mm x 6mm N.S. flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/fittings, bolts, nuts and washers etc. (as per drawing) and painting with primer and finish paint as required.	4.00	Sets			0.00	INR Zero Only
1.06	Erection of double pole 3 wire cross arm for 11KV/ 22KV/ 33 KV over head lines as required.	4.00	Nos.			0.00	INR Zero Only

1.07	Supplying and erection of 11 KV pin insulator complete with large steel head G.I. pin, nuts washers etc. as required.	36.00	Nos.			0.00	INR Zero Only
1.08	Supplying and erection of 11KV disc insulator for 11KV overhead lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required (Polymer type)	17.00	Nos.			0.00	INR Zero Only
1.09	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 mm diameter and above including binding etc. as required (10 Span x 3 wire x 50 mtr X 0.394 kg = 591 kgs	591.00	Kgs			0.00	INR Zero Only
1.10	Supply of G.I 8 SWG including binding etc. as required Supply of G.I Wire =100 X 50m X 3W =1500m X 0.103 kg/m=154.5 Kgs	154.50	Kgs			0.00	INR Zero Only
1.11	Erection of G.I wire	154.50	Kgs			0.00	INR Zero Only
1.12	Dismantling of over head lines comprising of copper/ aluminium over head conductor, G.I. wire, cross arms, insulators etc. as required.	330.00	Kgs			0.00	INR Zero Only
1.13	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required.	10.00	Nos.			0.00	INR Zero Only
1.14	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) V shape cross arm for two 11 KV over head line conductors complete with 50 mm X 6mm M.S. flat iron clamps, bolts and nuts including drilling holes for insulator pins, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required.	4.00	Nos.			0.00	INR Zero Only
2	Total impact of GST for the purpose of CTC	1	No.		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					