

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL						
Name of the Work / Contract No:		Work of " Replacing damaged cement poles and bulging conductors with steel tubular poles and new 55 sq mm rabbit conductors to make the work last longer, be safer, and be more reliable during the rainy season at Balumath and Bukru siding under Magadh OCP, M-S Area."		NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/25-26/04; Dated:- 10.04.2025.		
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of metallic pole of length above 10mtr and upto 12 mtr in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation Including excavation and refilling etc. as required.(19+7)	26	nos		0.00	INR Zero Only
2	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required.	21	Set		0.00	INR Zero Only
3	Erection of angle Iron/channel iron cross arm on wood/RCC/PCC/steel tubular or Rail pole for 4 wire system.	21	Set		0.00	INR Zero Only
4	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 2 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required.	21	Set		0.00	INR Zero Only
5	Erection of angle Iron/channel iron cross arm on wood/RCC/PCC/steel tubular or Rail pole for 2 wire system.	21	Set		0.00	INR Zero Only
6	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc. as required.	90	Set		0.00	INR Zero Only
7	Supplying and erection of 100 mm X 110 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required.	40	Set		0.00	INR Zero Only
8	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, bow tightener, 7/3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	10	Set		0.00	INR Zero Only
9	Erection of G.I wire no-6/8 SWG including binding etc.as required for cage cradle and crosslacing.	3	span		0.00	INR Zero Only
10	Painting with aluminium paint of approved brand and 10 manufacture to give an even shade. Two or more coats on new work.	26	Each		0.00	INR Zero Only
11	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required for Tensioning of Conductor where required.during changing of damaged insulators or changing of cross arms	699	Kg		0.00	INR Zero Only
12	Providing of 70 sq mm 4 core isi marked, upto 1.1 kv grade Alluminium armouredcable for laying service wire	30	Mtr		0.00	INR Zero Only
13	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of size not exceeding 35 to 95 sqmm direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. As required	20	Mtr		0.00	INR Zero Only
14	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words				INR Zero Only		