

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL

Name of the Work / Contract No:

Work of " Fitting of double compression nickel-plated brass cable gland with end termination by heat shrinking kit of bus bar panels installed in diesel generators and transformers at Balumath, Bukru & Phulbasiya siding for earthing of armoured power cable to prevent leakage current causing damage to equipment and harming people under Magadh OCP, M-S Area."

NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/25-26/05; Dated:- 11.04.2025.

Category of Services (To Be Selected by Department)

Category of Bidder (To Be Selected by Bidder)

ITC Available

Works Contract

Bidder's Status (Mandatory)

Total GST(in Rs.)

GST to be Paid By Bidder (in Rs.)

GST to be Paid By CIL/Subsidiary (in Rs.)

Name of the Bidder/ Bidding Firm / Company :

Select

0.00

0.00

0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Supplying and making straight through joint with cast resin compound including ferrules and other jointing materials for following size 1 of PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1 KV grade as required for end termination in tubular pole upto 35 sq mm cable. For tubular poles installed in weighbridges and tower lights	20	nos		0.00	INR Zero Only
2	Supplying and making straight through joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1 KV grade as required for end termination in tubular pole upto core 70 sq mm cable. For Generator power cable and Transformer power cable and various establishments	30	Set		0.00	INR Zero Only
3	Supplying of double compression nickle plated brass cable glands for following size of PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1 KV grade as required.4 C x 35 sq mm(31 mm)	20	nos		0.00	INR Zero Only
4	Supplying of double compression nickle plated brass cable glands for following size of PVC Insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1 KV grade as required.4 C x 70 sq mm(38 mm)	30	nos		0.00	INR Zero Only
5	600 mm X 600 mm X 6 mm thick G.I. plate for fixing of gland and making of 31 mm or 38 mm dia hole by drilling or welding as required for Generator and Tower light pannels.	20	nos		0.00	INR Zero Only
6	Removing previously connected cables from over head line, Generetor panel and cleaning cable to be suitable for Glanding and Termination and again Connecting the cable in proper sequence with Proper fixing of GI plate in proper hole of 31 mm or 38 mm dia.	50	Job		0.00	INR Zero Only
7	Providing of 70 sq mm 4 core isi marked, upto 1.1 kv grade Alluminium armouredcable for changing of service cable where ever required.	30	Mtr		0.00	INR Zero Only
8	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of size not exceeding 35 to 95 sqmm direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. As required	30	Mtr		0.00	INR Zero Only
9	Providing of 35 sq mm 4 core isi marked, upto 1.1 kv grade Alluminium armouredcable for changing of service cable where ever required.	30	Mtr		0.00	INR Zero Only
10	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of size upto 35 sqmm direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. As required	30	Mtr		0.00	INR Zero Only
11	Earthing with copper earth plate 600 mm X 600mm X 3 mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 mtr. Long etc.with charcoal/coke and salt as required For tubular pole installed in weighbriages wherever required.	10	nos		0.00	INR Zero Only
12	Providing and fixing 25mmX5mm GI.strip on surface or in recess for connections etc. as required.	50	Mtr		0.00	INR Zero Only
13	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				