

Validate

Print

Help

**Item Rate BoQ**

Tender Inviting Authority: Staff Officer Civil Piparwar Area.

Name of the Work : Filling of potholes, ditches of roads withstone dust and metaal from Police picket to weigh bridge no 15 under Ashok OCP, Piparwar and providing and fixing RCC hume pipes across haul road at locations where cross drainage is required and garland drain cutting around OB dump area under Ashok OCP.

.	Category of Services (To Be Selected by Department)	Category of Bidder ( To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Plant Mix Method (Construction of granular sub-base by providing close graded Material, mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 ) for grading -I material	489.00	Cum			0.00	INR Zero Only
1.02	Plant Mix Method (Construction of granular sub-base by providing close graded Material, mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 ) for grading -III material	489.00	Cum			0.00	INR Zero Only
1.03	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for a lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.2.8.1All kinds of soil.	573.75	cum			0.00	INR Zero Only

1.04	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C.pipes including collars / spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement:2 fine sand) including testing of joints etc. Complete 1200 mm dia RCC pipes. (Laying by manual/ mechanical means)	212.50	MTR			0.00	INR Zero Only
1.05	Filling available excavated earth (excluding rock) in trenches, plinth. Sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and for all lift	333.62	cum			0.00	INR Zero Only
1.06	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5m in width as well as 10sqm on plan) including getting out and disposal of excavated earth lead upto 50m and for all lift, as directed by Engineer-in-charge. All kinds of soil	5287.95	cum			0.00	INR Zero Only
1.07	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos		0.00	0.00	INR Zero Only
<b>Total in Figures</b>						0.00	INR Zero Only
<b>Quoted Rate in Words</b>		<b>INR Zero Only</b>					