

ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	(A). Repairing of 3.3KV, 630A, VCB, CTR 600/300/5A, make-PCE, Sl.No.-05/HMV/132 installed at main sub-station of <b>GVP Phase-II OCP</b> Providing of tripping coil 110V	1.00	Set			0.00	INR Zero Only
1.02	Providing of volt meter 4" x 4", 3.3KV/110V	1.00	Set			0.00	INR Zero Only
1.03	Providing of main moving contact (as per sample)	2.00	Sets			0.00	INR Zero Only
1.04	Providing of main fixed contact 400A (as per sample)	3.00	Sets			0.00	INR Zero Only
1.05	Providing of control circuit wire 1.5 sq.mm	30.00	Mtrs.			0.00	INR Zero Only
1.06	Labour Cost	1.00	L.S			0.00	INR Zero Only
1.07	(B). Repairing of 3.3KV VCB, make-PCE, 630A, Sl.No.-05/HMV/131 of secondary switch at 3MVA, 11KV/3.3KV transformer of <b>GVP Phase-II OCP</b> Providing of 3.3KV HT Bushing with stud, washer and nut etc	4.00	Nos.			0.00	INR Zero Only
1.08	Providing of diode bridge DC-110V	1.00	No.			0.00	INR Zero Only
1.09	Providing of shunt trip coil DC-110V	1.00	No.			0.00	INR Zero Only
1.10	Providing of HRC fuse & link 16A	4.00	Nos.			0.00	INR Zero Only
1.11	Providing of P.T Fuse 3A	2.00	Nos.			0.00	INR Zero Only
1.12	Providing of Indicator lamp with holder	3.00	Nos.			0.00	INR Zero Only
1.13	Pump body inside and outside rust & dust cleaning, painting	1.00	Set			0.00	INR Zero Only
1.14	C.I Casting gland new making as per sample	1.00	No.			0.00	INR Zero Only
1.15	Gun metal casting bush bearing new making (as per sample)	1.00	Set			0.00	INR Zero Only
1.16	Labour cost	1.00	L.S			0.00	INR Zero Only
1.17	(C). Repairing and re-conditioning of 3.3KV VCB, 630A (Filed Switch), Sl.No.-0365, make-Andrew Yule of <b>GVP Phase-II OCP</b> Providing of 3.3KV HT Bushing with stud, washer & nut etc	4.00	Nos.			0.00	INR Zero Only
1.18	Providing of shunt trip coil DC-110V	1.00	No.			0.00	INR Zero Only
1.19	Providing of HRC fuse & link 16A	4.00	Nos.			0.00	INR Zero Only
1.20	Providing of P.T Fuse 3A	2.00	No.			0.00	INR Zero Only
1.21	Providing of Indicator lamp with holder	3.00	No.			0.00	INR Zero Only

1.22	Providing of E/F, O.C relay (IDMT) 110V	1.00	No.			0.00	INR Zero Only
1.23	Labour Cost	1.00	L.S			0.00	INR Zero Only
1.24	<b>(D). Repairing of 3.3KV, 630A, VCB CTR: 600/300/5A, make-PCE, Sl. No.-05/HMV/134 Installed at Filter bed sub-station of GVP Phase-II OCP</b> IDMT relay, electronic type, 110V AC/DC, minimum Instantaneous over current setting 200% and minimum Earth fault setting - 50%	1.00	No.			0.00	INR Zero Only
1.25	Providing of selector switch 16A Voltmeter	1.00	No.			0.00	INR Zero Only
1.26	Providing of selector switch 16A Ammeter	1.00	No.			0.00	INR Zero Only
1.27	Auxiliary Contactor 3 NO + 3 NC	1.00	No.			0.00	INR Zero Only
1.28	PVC cable 1.5sq.mm for wiring of control circuit with required ferruls and lugs	60.00	Mtrs.			0.00	INR Zero Only
1.29	Labour Cost	1.00	L.S			0.00	INR Zero Only
1.30	<b>(E).Repairing &amp; Re-conditioning of 3.3KV VCB, 800 Amp. Sl.No-514 make-meditron, of GVP Ph-II OCP.</b> Providing of earth leakage relay Aux supply 110V Ac	1.00	No.			0.00	INR Zero Only
1.31	Providing of IDMT relay with 2 O/C + 1E/F, AC/DC 110V, 5A	1.00	No.			0.00	INR Zero Only
1.32	Providing of selector switch of Ammeter and Voltmeter	2.00	Nos.			0.00	INR Zero Only
1.33	Providing of closing coil 110V DC	1.00	Nos.			0.00	INR Zero Only
1.34	Providing of 3.3KV bushing with studs	2.00	Nos.			0.00	INR Zero Only
1.35	Providing of single core copper wire 1.5 sq.mm PVC 50mtr	50.00	Mtrs.			0.00	INR Zero Only
1.36	Labour Cost	1.00	L.S			0.00	INR Zero Only
1.37	<b>(F). Repairing of VCB, 400 A, PTR-3.3KV/110V PEC, CTR-400/5A Sl.2005/HMV/95 make PCE Installed Zero point of GVP Phase-11 OCP.</b> IDMT relay, electronic type, 110V AC/DC, minimum Instantaneous over current setting 200% and minimum Earth fault setting - 50%	1.00	No.			0.00	INR Zero Only
1.38	Ammeter 4" size(square) 400/5A	1.00	No.			0.00	INR Zero Only
1.39	Providing of selector switch 16A Voltmeter	1.00	No.			0.00	INR Zero Only
1.40	Providing of selector switch 16A Ammeter	1.00	No.			0.00	INR Zero Only
1.41	Auxiliary Contactor 3 NO + 3 NC	1.00	No.			0.00	INR Zero Only
1.42	PVC cable 1.5sq.mm for wiring of control circuit with required ferruls and lugs	60.00	Mtrs.			0.00	INR Zero Only
1.43	Labour Cost	1.00	L.S			0.00	INR Zero Only
1.44	<b>(G). Repairing &amp; Re-conditioning of 11KV VCB, 630 Amp. make-PCE, Sl.No.-2004/HMV/46 of main sub-station of GVP Ph-II OCP.</b> Providing of IDMT relay with 2 O/C + 1E/F, AC/DC 110V, 5A	1.00	No.			0.00	INR Zero Only
1.45	Providing of HD Resin Cast current Transformer 150/75/5 +5Amp.	1.00	No.			0.00	INR Zero Only

1.46	Providing of selector switch of Ammeter and Voltmeter	2.00	Nos.			0.00	INR Zero Only
1.47	Providing of closing coil 110V DC	1.00	No.			0.00	INR Zero Only
1.48	Providing of 3.3KV bushing with studs	2.00	Nos.			0.00	INR Zero Only
1.49	Providing of single core copper wire 1.5 sq.mm PVC 50mtr	50.00	Mtrs.			0.00	INR Zero Only
1.50	Labour cost	1.00	L.S			0.00	INR Zero Only
1.51	<b>(H). Repairing of VCB, 400 A, CTR-100/5A, make Meditron, SL.No. 516 Installed Zero point of GVP Ph- II OCP.</b> Providing of 3.3KV HT Bushing with stud, washer & nut etc	3.00	Nos.			0.00	INR Zero Only
1.52	Providing of shunt trip coil DC-110V	1.00	No.			0.00	INR Zero Only
1.53	Providing of HRC fuse & link 16A	4.00	Nos.			0.00	INR Zero Only
1.54	Providing of P.T Fuse 3A	1.00	No.			0.00	INR Zero Only
1.55	Auxiliary Contactor 3 NO + 3 NC	1.00	No.			0.00	INR Zero Only
1.56	Pump body inside and outside rust & dust cleaning, painting	1.00	Set			0.00	INR Zero Only
1.57	C.I Casting gland new making as per sample	1.00	No.			0.00	INR Zero Only
1.58	Labour Cost	1.00	L.S			0.00	INR Zero Only
1.59	<b>(I). Repairing of 3.3KV, 400A VCB, CTR 100/5A, make-Electro Technica, SL.No.-7964 installed at zero point of GVP Ph-II OCP</b> Voltmeter 4" size square, 3.3KV/110V	1.00	No.			0.00	INR Zero Only
1.60	Ammeter 4" size(square) 400/5A	1.00	No.			0.00	INR Zero Only
1.61	Providing of selector switch 16A Voltmeter	1.00	No.			0.00	INR Zero Only
1.62	Providing of selector switch 16A Ammeter	1.00	No.			0.00	INR Zero Only
1.63	Auxiliary Contactor 3 NO + 3 NC	1.00	No.			0.00	INR Zero Only
1.64	PVC cable 1.5sq.mm for wiring of control circuit with required ferruls and lugs	50.00	Mtrs.			0.00	INR Zero Only
1.65	C.I Casting gland new making as per sample	1.00	No.			0.00	INR Zero Only
1.66	Labour cost	1.00	L.S			0.00	INR Zero Only
2	<b>Total impact of GST for the purpose of CTC</b>	1	No.		0.00	0.00	INR Zero Only
<b>Total in Figures</b>						0.00	INR Zero Only

Quoted Rate in Words	INR Zero Only
----------------------	---------------