

Tender Inviting Authority: Staff officer (E&M), Amrapali- Chandragupta Area, CCL					
Name of the Work / Contract No:	Revival and re-conditioning of street lighting from zero point to weighbridge No. 06 with strengthening of poles at Amrapali OCP under A-C Area		NIT No: G.M.(A-C)/S.O.(E&M)/e-NIT/25-26/02 ; Dated: 16.04.2025		
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required.	10.000	Each		0.00	INR Zero Only
2	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required. Above 10.00 metre and upto 12.00 metre	10.000	Each		0.00	INR Zero Only
3	Exacavation work by mechancial means (Hydraulic excavator)/ manual Means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sq.m on plan) including dreesing of sides and ramming of bottoms, lift upto 1.5m, including geeting out the excavated soil and disposal of surplus excavavted soils as directed, within a lead of 50m. hrad rock (blasting prohibited)	15.00	Cum		0.00	INR Zero Only
4	Providing and making steel pole collar with cement concrete (1 cement : 3 coarse sand : 6 stone aggregate 20mm) of specified size and shape including form work, plastering if required, curing etc as required. (volume of pole/ pipe not to be deducted)	15.00	Cum		0.00	INR Zero Only

5	Supplying and embedding following dia G.I. pipe (medium class) in pole collar/ foundation (during casting) for cable entry including bending the pipe to the required shape complete as required. 40 mm dia	60.00	Mtr.		0.00	INR Zero Only
6	Supplying and fixing of 32 mm dia X 2.00 metres long G.I. pipe (medium class) bracket for mounting of fluorescent / HPMV / HPSV street light fitting on pole including bending the pipe to the required shape, 2 nos 40 mm X 3 mm flat iron clamps with nuts, bolts and washer, painting the flat iron with primer and finish paint etc. as required.	18.00	Set		0.00	INR Zero Only
7	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. Upto 35 sq. mm	200.00	Mtr.		0.00	INR Zero Only
8	Providing & replacement of armoured cable 16 sq.mm 4 Core	200.00	Mtr.		0.00	INR Zero Only
9	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				