

Name of the Work - "[A] Erection and Installation of fixed fabricated lighting towers; [B] Installation of Tanker filling point for re-filling water to tanker for dust suppression [C] Dismantling of Pole mounted transformer from existing D.P. Structure and erection on the proposed D.P. Structure"at different locations of mines of Rajrappa Project on as , when and where required basis for a period of 6 months".

ITC Available

Sl .No	Description	Quantity	Units	Rate
1	Erection and Installation of fixed fabricated lighting towers.	6	nos	
2	Providing and fixing of foundation HT bolts with nut and washer 1"X12" (Dia. X Length).	96	nos	
3	Erection of Tanker filling points at different locations,	6	set	
4	Making deep bore hole of 150mm dia., deep per ft. for each earthpit.	42	feet	
5	Supply and erection of approved make safe earthing electrode consisting pipe-in-pipe technology as per IS 3043-1987 made of corrosion free G.L. pipes with constant ohmic value surrounded by highly conductive compound with high charge dissipation suitable for effective and maintenance free earthing in earth pit of minimum bore dia. 150mm size, as mentioned below:	6	nos	
6	Providing and fixing 25 mm X5 mm G.I. strip on surface or in recess for connections etc. as required.	18	meter	
7	providing masonry enclosure with cover plate having locking arrangement and as required	4	set	
8	Dismantling of Pole mounted outdoor lighting transformer from existing D.P. Structure and re-erection on the proposed D.P. Structure including erection of required Channel, Angle brackets and clamps.	10	set	
9	Erection and Installation of fixed fabricated lighting towers.	6	nos	
10	Total impact of gst	1	no	
11	Total	1	no	

