

Validate

Print

Help

**Item Rate BoQ**

Tender Inviting Authority: Staff officer (E&amp;M), NK Area, CCL

Name of the Work / Contract No:	Repairing of 05 Nos. of 6.6kV DOL Starter, Make Sait Mine Line Pvt. Ltd and 02 Nos. 6.6kV DOL starter, Make Prot India for operation of pumps at Jehlitand sump and Main Sump under KDH OCP, NK Area		NIT No. GM (NK)/EnM/eNIT/2025-26/23; dated 26.04.2025.		
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Repairing of 6.6kV DOL Starter, Make Sait Minline Pvt. Ltd, Sl. No. SA 1874.					
2	Providing and fixing of closing coil, 220V	1.00	Nos		0.00	INR Zero Only
3	Providing and fixing of push button 22.5 mm dia with 1 NO + 1 NC element.	3.00	Nos		0.00	INR Zero Only
4	Providing and fixing of Isolator Limit Switch 1 NO + 1 NC	1.00	Nos		0.00	INR Zero Only
5	Providing and fixing of Indicating Lamp 220V	2.00	Nos		0.00	INR Zero Only
6	Providing and fixing of Auxiliary Contractor 3 NO + 1 NC, 220V	1.00	Nos		0.00	INR Zero Only
7	Repairing of Isolator set with required materials (A) Repairing and checking of operating Mechanism (B) Repairing of moving contact © Repairing of fixed contact.	1.00	Nos		0.00	INR Zero Only
8	Providing and fixing of Potential Transformer 6.6kV/ 220V, 300 VA	1.00	Nos		0.00	INR Zero Only

9	Providing and fixing of Post insulator, 6.6 kV grade	9.00	Nos		0.00	INR Zero Only
10	Providing and fixing of resin cast CBCT	1.00	Nos		0.00	INR Zero Only
11	Providing and fixing of Earth Leakage Relay, 220 V	1.00	Nos		0.00	INR Zero Only
12	Complete denting, painting (Outside and inside) and welding of starter with providing of locking system	1.00	Nos		0.00	INR Zero Only
13	<b>Repairing of 6.6kV DOL Starter, Make Sait Mineline Pvt. Ltd, Sl. No. SA 1875.</b>					
14	Providing and fixing of HT Control Fuse, 3A	3.00	Nos		0.00	INR Zero Only
15	Providing and fixing of Vacuum Contactor Rectifier Bridge.	1.00	Nos		0.00	INR Zero Only
16	Providing and fixing of 400A Copper bus bar set of three	1.00	Set		0.00	INR Zero Only
17	Providing and fixing of 72 sqmm Ammeter, 100/5A	1.00	Nos		0.00	INR Zero Only
18	Providing and fixing of push button 22.5 mm dia with 1 NO + 1 NC element.	2.00	Nos		0.00	INR Zero Only
19	Providing and fixing of Indicating Lamp 220V	1.00	Nos		0.00	INR Zero Only
20	Providing and fixing of Isolator Limit Switch 1 NO + 1 NC	1.00	Nos		0.00	INR Zero Only
21	Providing and fixing of Potential Transformer 6.6kV/ 220V, 300 VA	1.00	Nos		0.00	INR Zero Only
22	Providing and fixing of Post insulator, 6.6 kV grade	6.00	Nos		0.00	INR Zero Only
23	Providing and fixing of Holding Coil, 220V	1.00	Nos		0.00	INR Zero Only
24	Complete denting, painting (Outside and inside) and welding of starter with providing of locking system	1.00	Nos		0.00	INR Zero Only
25	<b>Repairing of 6.6kV DOL Starter, Make Sait Mineline Pvt. Ltd, Sl. No. SA 1876.</b>					
26	Providing and fixing of push button 22.5 mm dia with 1 NO + 1 NC element.	2.00	Nos		0.00	INR Zero Only
27	Providing and fixing of Indicating Lamp 220V	2.00	Nos		0.00	INR Zero Only
28	Providing and fixing of 72 sqmm Ammeter, 100/5A	1.00	Nos		0.00	INR Zero Only
29	Providing and fixing of Post insulator, 6.6 kV grade	6.00	Nos		0.00	INR Zero Only
30	Providing and fixing of Holding Coil, 220V	1.00	Nos		0.00	INR Zero Only

31	Providing and fixing of Earth Leakage Relay, 220 V	2.00	Nos		0.00	INR Zero Only
32	Providing and fixing of resin cast CBCT	1.00	Nos		0.00	INR Zero Only
33	Checking and fixing of Vacuums Interrupter with required materials	1.00	Nos		0.00	INR Zero Only
34	Repairing of Isolator set with required materials (A) Repairing and checking of operating Mechanism (B) Repairing of moving contact © Repairing of fixed contact.	1.00	Nos		0.00	INR Zero Only
35	Complete wiring with ferrule, Lugs, tapes etc and all circuit checking	1.00	Nos		0.00	INR Zero Only
36	<b>Repairing of 6.6kV DOL Starter, Make Sait Mineline Pvt.</b>					
37	Providing and fixing of closing coil, 220V	1.00	Nos		0.00	INR Zero Only
38	Providing and fixing of Isolator Limit Switch 1 NO + 1 NC	1.00	Nos		0.00	INR Zero Only
39	Providing and fixing of Auxiliary Contractor 3 NO + 1 NC, 220V	1.00	Nos		0.00	INR Zero Only
40	Providing and fixing of isolator Set 400A, 6.6 kV On-off	1.00	Nos		0.00	INR Zero Only
41	Providing and fixing of Post insulator, 6.6 kV grade	3.00	Nos		0.00	INR Zero Only
42	Providing and fixing of Earth Leakage Relay, 220 V	1.00	Nos		0.00	INR Zero Only
43	Complete denting, painting (Outside and inside) and welding of starter with providing of locking system	1.00	Nos		0.00	INR Zero Only
44	<b>Repairing of 6.6kV DOL Starter, Make Sait Mineline Pvt.</b>					
45	Providing and fixing of Vacuum Contactor Rectifier Bridge.	1.00	Nos		0.00	INR Zero Only
46	Providing and fixing of push button 22.5 mm dia with 1 NO + 1 NC element.	3.00	Nos		0.00	INR Zero Only
47	Providing and fixing of Auxiliary Contractor 3 NO + 1 NC, 220V	1.00	Nos		0.00	INR Zero Only
48	Providing and fixing of isolator Set 400A, 6.6 kV On-off	1.00	Nos		0.00	INR Zero Only
49	Providing and fixing of resin cast CT, 100/5A	3.00	Nos		0.00	INR Zero Only
50	Complete denting, painting (Outside and inside) and welding of starter with providing of locking system	1.00	Nos		0.00	INR Zero Only
51	<b>Repairing of 6.6kV DOL Starter, Make Prot India, Local Sl. No. KDH/ENM/Starter/01</b>					
52	Providing and fixing of closing coil, 220V	1.00	Nos		0.00	INR Zero Only

53	Providing and fixing of Vacuum Contactor Rectifier Bridge.	1.00	Nos		0.00	INR Zero Only
54	Providing and fixing of push button 22.5 mm dia with 1 NO + 1 NC element.	3.00	Nos		0.00	INR Zero Only
55	Providing and fixing of Isolator Limit Switch 1 NO + 1 NC	1.00	Nos		0.00	INR Zero Only
56	Providing and fixing of Indicating Lamp 110V	2.00	Nos		0.00	INR Zero Only
57	Providing and fixing of Auxiliary Contractor 3 NO + 1 NC, 220V	1.00	Nos		0.00	INR Zero Only
58	Providing and fixing of 72 sqmm Voltmeter, 0-10kV, 6.6kV/110V	1.00	Nos		0.00	INR Zero Only
59	Providing and fixing of resin cast CT, 100A/5A	3.00	Nos		0.00	INR Zero Only
60	Providing and fixing of CT operated Thermal Overload relay	1.00	Nos		0.00	INR Zero Only
61	Providing and fixing of HRC Fuse Link 4A for control	2.00	Nos		0.00	INR Zero Only
62	Providing and fixing of resin cast CBCT	1.00	Nos		0.00	INR Zero Only
63	Providing and fixing of Earth Leakage Relay, 220 V	1.00	Nos		0.00	INR Zero Only
64	Complete denting, painting (Outside and inside) and welding of starter with providing of locking system	1.00	Nos		0.00	INR Zero Only
65	<b>Repairing of 6.6kV DOL Starter, Make Prot India, Local Sl. No. KDH/ENM/Starter/02</b>					
66	Providing and fixing of Vacuum Contactor Rectifier Bridge.	1.00	Nos		0.00	INR Zero Only
67	Providing and fixing of Isolator Limit Switch 1 NO + 1 NC	1.00	Nos		0.00	INR Zero Only
68	Providing and fixing of Auxiliary Contractor 3 NO + 1 NC, 220V	1.00	Nos		0.00	INR Zero Only
69	Repairing of Isolator set with required materials (A) Repairing and checking of operating Mechanism (B) Repairing of moving contact © Repairing of fixed contact.	1.00	Nos		0.00	INR Zero Only
70	Providing and fixing of Post insulator, 6.6 kV grade	3.00	Nos		0.00	INR Zero Only
71	Providing and fixing of 72 sqmm Ammeter, 100A/5A	1.00	Nos		0.00	INR Zero Only
72	Providing and fixing of 72 sqmm Voltmeter, 0-10kV, 6.6kV/110V	1.00	Nos		0.00	INR Zero Only
73	Providing and fixing of resin cast CT, 100A/5A	3.00	Nos		0.00	INR Zero Only

74	Providing and fixing of HRC Fuse Link 4A for control	2.00	Nos		0.00	INR Zero Only
75	Providing and fixing of resin cast CBCT	1.00	Nos		0.00	INR Zero Only
76	Providing and fixing of Earth Leakage Relay, 220 V	1.00	Nos		0.00	INR Zero Only
77	Complete denting, painting (Outside and inside) and welding of starter with providing of locking system	1.00	Nos		0.00	INR Zero Only
78	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				