

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL

Name of the Work / Contract No:

Work of " Power supply arrangement at newly made check post in transporting road for Dewalgadda village bypass near Birsamunda chowk Dewalgadda by extension of overhead line from Weighbridge number -5 under Magadh OCP.M-S Area."

NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/25-26/06; Dated:- 21.04.2025.

Category of Services (To Be Selected by Department)

Category of Bidder (To Be Selected by Bidder)

ITC Available

Works Contract

Bidder's Status (Mandatory)

Total GST(in Rs.)

GST to be Paid By Bidder (in Rs.)

GST to be Paid By CIL/Subsidiary (in Rs.)

Name of the Bidder/ Bidding Firm / Company :

Select

0.00

0.00

0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of metallic pole of length above 10mtr and upto 12 mtr in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required	17	nos		0.00	INR Zero Only
2	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above Including binding etc. as required for Tensioning of Conductor where required.during changing of damaged insulators or changing of cross arms	432	Kg		0.00	INR Zero Only
3	Erection of angle Iron/channel iron cross arm on wood/RCC/PCC/steel tubular or Rail pole for 4 wire system.	14	Set		0.00	INR Zero Only
4	Supplying of channel iron 75 mm X 40 mm x 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required	14	Set		0.00	INR Zero Only
5	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 2 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required	14	Set		0.00	INR Zero Only
6	Erection of angle Iron/channel iron cross arm on wood/RCC/PCC/steel tubular or Rail pole for 2 wire system.	14	Set		0.00	INR Zero Only
7	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc. as required.	55	Set		0.00	INR Zero Only
8	Supplying and erection of 100 mm X 110 mm shackle insulator with G: I. Bolt, nuts and straps etc. as required.	30	Set		0.00	INR Zero Only
9	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, bow tightener, 7/3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required	5	Set		0.00	INR Zero Only
10	Providing of 25 sq mm 4 core isi marked, upto 1.1 kv grade Alluminium armouredcable for laying service wire	50	Mtr		0.00	INR Zero Only
11	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of size not exceeding 35 sqmm direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. As required	10	Mtr		0.00	INR Zero Only
12	Providing of Onload Manual switch disconnector changer with sheet steel enclosure Type, 100 Amp	2	Each		0.00	INR Zero Only
13	Providing and fixing 100 A rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required.	2	Each		0.00	INR Zero Only
14	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper busbar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)6 way, Double door	2	Each		0.00	INR Zero Only
15	Erection of cradle guard as required.	2	Each		0.00	INR Zero Only
16	Painting with aluminium paint of approved brand and manufacture to give an even shade. Two or more coats on new work.	17	Each		0.00	INR Zero Only
17	Fixing Charge of supplied items including end termination no 12 at 15% of item cost	1	Job		0.00	INR Zero Only
18	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				