

**Bill of quantity for the work Filling of Illegal mines under different projects of Barka-Sayal Area under GM Unit, Barka-Sayal Area'.**

<b>S.N.</b>	<b>Particular of work</b>	<b>Qnty.</b>	<b>Unit</b>	<b>Updated Rate</b>	<b>Amount</b>
1	Excavating, supplying and filling of local earth (Excluding royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.	1810.00	cum	255.72	462853.20
		<b>Total</b>			462853.20
		<b>Add GST @ 18%</b>			83313.58
		<b>Total cost Rs.</b>			546166.78