

| Validate | | Print | | Help | | Percentage BoQ | |
|---|---|----------|---|-----------------------------|-----------------------------------|--|--|
| Tender Inviting Authority: Staff Officer (Civil),CCL, Dhori Area | | | | | | | |
| Name of Work:- Repair maintenance and renovation of central hospital Dhori Area under Gm Unit Dhori Area | | | | | | | |
| | Category of Services (To Be Selected by Department) | | Category of Bidder(To Be Selected by Bidder) | To Be Entered by Department | | | |
| ITC Not Available | Works Contract | | Bidder's Status (Mandatory) | Rate of GST (in %) | GST to be Paid By Bidder (in Rs.) | GST to be Paid By CIL/Subsidiary (in Rs.) | |
| Name of the Bidder/ Bidding Firm / Company : | | | Select | 18.00 | 0.00 | 0.00 | |
| <p align="center">PRICE SCHEDULE</p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p> | | | | | | | |
| NUMBER # | TEXT # | NUMBER # | TEXT # | NUMBER | NUMBER # | TEXT # | |
| Sl. No. | Item Description | Quantity | Units | Estimated Rate in Rs. P | TOTAL AMOUNT in Rs. P | TOTAL AMOUNT In Words | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | |
| 1 | Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil. | 119.55 | Cum | 188.45 | 22529.20 | INR Twenty Two Thousand Five Hundred & Twenty Nine and Paise Twenty Only | |
| 2 | Supplying and filling in plinth with Jamuna sand under floors including, watering, ramming consolidating and dressing complete. | 0.23 | Cum | 1844.00 | 424.12 | INR Four Hundred & Twenty Four and Paise Twelve Only | |
| 3 | Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering -All work upto plinth level: 1:3:6 (1 Cement: 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) | 0.45 | Cum | 5916.00 | 2662.20 | INR Two Thousand Six Hundred & Sixty Two and Paise Twenty Only | |
| 4 | Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level: 1:1.5:3 (1 cement: 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size) | 3.20 | Cum | 7365.50 | 23569.60 | INR Twenty Three Thousand Five Hundred & Sixty Nine and Paise Sixty Only | |

| | | | | | | |
|----|--|---------|-----|----------|-----------|---|
| 5 | Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars | 1316.39 | kg | 75.85 | 99848.18 | INR Ninety Nine Thousand Eight Hundred & Forty Eight and Paise Eighteen Only |
| 6 | Centring and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete. | 12.80 | Sqm | 262.55 | 3360.64 | INR Three Thousand Three Hundred & Sixty and Paise Sixty Four Only |
| 7 | Providing and fixing mild steel round holding down bolts with nuts and washer plates complete. | 227.52 | kg | 75.35 | 17143.63 | INR Seventeen Thousand One Hundred & Forty Three and Paise Sixty Three Only |
| 8 | Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. | 6164.86 | Kg | 92.55 | 570557.79 | INR Five Lakh Seventy Thousand Five Hundred & Fifty Seven and Paise Seventy Nine Only |
| 9 | Manufacturing supplying and fixing retro reflective overhead signage boards made up of 2mm thick aluminium sheet face to be fully covered with high intensity and encapsulated lens type heat activated retro reflective sheeting conforming to type -III of ASTM-D-4956-01 as approved by Engineer-in-charge letters, borders etc. as per IRC : 67-2001 in silver white with blue colour back ground and with high intensity grade, pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming to class II of ASTM-D-4956-01 and fixing the same to the plate of structural frame work by means of suitable sized aluminium alloys, rivets or bolts & nuts @ 300 mm centre to centre all along the periphery as well as in two vertical rows alongwith theft resistant measures including the cost of painting with two'or | 19.20 | sqm | 4,849.00 | 93100.80 | INR Ninety Three Thousand One Hundred and Paise Eighty Only |
| 10 | Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work | 93.14 | Sqm | 99.90 | 9304.69 | INR Nine Thousand Three Hundred & Four and Paise Sixty Nine Only |

| | | | | | | |
|----|---|-------|-----|---------|----------|---|
| 11 | Manufacturing supplying and fixing retro reflective sign boards made up of 2mm thick aluminium sheet, face to be fully covered with high intensity encapsulated type heat activated retro reflective sheeting conforming to type - IV of ASTM-D 4956-01 in blue and silver white or other colour combination including subject matter, message (bi-lingual), symbols and borders etc. as per IRC ; 67:2001, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class -2 of ASTM-D-4956-01 and fixing the same with suitable sized aluminium alloy rivets @ 20 cm c/c to back support frame of M.S. angle iron of size 25x25x3 mm alongwith theft resistant measures, mounted and fixed with 2 Nos. M.S. angles of size 35x35x5 mm to a vertical post made up of M.S. Tee section | 15.26 | sqm | 5457.30 | 83278.40 | INR Eighty Three Thousand Two Hundred & Seventy Eight and Paise Forty Only |
| 12 | Manufacturing supplying and fixing retro reflective sign boards made up of 2mm thick aluminium sheet, face to be fully covered with high intensity encapsulated type heat activated retro reflective sheeting conforming to type - IV of ASTM-D 4956-01 in blue and silver white or other colour combination including subject matter, message (bi-lingual), symbols and borders etc. as per IRC ; 67:2001, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class -2 of ASTM-D-4956-01 and fixing the same with suitable sized aluminium alloy rivets @ 20 cm c/c to back support frame of M.S. angle iron of size 25x25x3 mm alongwith theft resistant measures, mounted and fixed with 2 Nos. M.S. angles of size 35x35x5 mm to a vertical post made up of M.S. Tee section | 10.17 | sqm | 4114.30 | 41842.43 | INR Forty One Thousand Eight Hundred & Forty Two and Paise Forty Three Only |

| | | | | | | |
|----|--|---------|------|---------|------------|--|
| 13 | Designing, Providing and Fixing Tensile Fabric Membrane of Architectural Membrane Make using Tensile Fabric Sattler Germany (or equivalent) 900 GSM, with providing, designing, bending, fixing and painting of required structural members all complete as per EIC. The rate also covers warranty of 10 years from the date of completion). | 3550.80 | Sqft | 592.37 | 2103387.40 | INR Twenty One Lakh Three Thousand Three Hundred & Eighty Seven and Paise Forty Only |
| 14 | P/F 60MM THICK FACTORY MADE C.C INTERLOCKING PAVER BLOCK OF M-30 GRADE MADE BY BLOCK MACKING MACHINE OVER AND I/C 50 MM THICK BED OF C SAND,FILLING THE JOINTS | 1670.00 | Sqm | 752.85 | 1257259.50 | INR Twelve Lakh Fifty Seven Thousand Two Hundred & Fifty Nine and Paise Fifty Only |
| 15 | Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand) | 49.34 | Cum | 6494.75 | 320450.97 | INR Three Lakh Twenty Thousand Four Hundred & Fifty and Paise Ninety Seven Only |
| 16 | Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size). | 7.23 | cum | 8797.65 | 63607.01 | INR Sixty Three Thousand Six Hundred & Seven and Paise One Only |
| 17 | Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size). | 4.05 | cum | 8356.10 | 33842.21 | INR Thirty Three Thousand Eight Hundred & Forty Two and Paise Twenty One Only |

| | | | | | | |
|----|---|---------|-----|----------|------------|--|
| 18 | Providing and fixing precoated galvanized iron profile sheets (size, shape and pitch of corrugation as 5% total coated thickness (TC T), Zinc coating 120gsm as per IS:277 in approved by Engineer-in-charge) 0.05 mm. 240 mpa mm steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces | 124.15 | Sqm | 571.00 | 70889.65 | INR Seventy Thousand Eight Hundred & Eighty Nine and Paise Sixty Five Only |
| 19 | Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand) | 22.50 | Cum | 5322.15 | 119748.38 | INR One Lakh Nineteen Thousand Seven Hundred & Forty Eight and Paise Thirty Seven Only |
| 20 | 12 mm cement plaster finished with a floating coat of neat cement of mix1:4 (1 cement: 4 fine sand) | 395.00 | Sqm | 284.75 | 112476.25 | INR One Lakh Twelve Thousand Four Hundred & Seventy Six and Paise Twenty Five Only |
| 21 | 12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand) . | 2394.68 | Sqm | 217.70 | 521321.84 | INR Five Lakh Twenty One Thousand Three Hundred & Twenty One and Paise Eighty Four Only |
| 22 | Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete.Size of Tile 60x60 cm | 1151.94 | sqm | 1,180.40 | 1359749.98 | INR Thirteen Lakh Fifty Nine Thousand Seven Hundred & Forty Nine and Paise Ninety Eight Only |

| | | | | | | |
|----|---|---------|-------|---------|------------|---|
| 23 | Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3mm thick water proofing membrane, black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 ltr/sqm. by the same membrane manufacturer of density at 25°C, 0.87 - 0.89 kg/ltr and viscosity 70 - 160 cps. Over the primer coat the layer of membrane shall be laid using butane torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 350/300 N/5cm. Tear strength in longitudinal and transverse direction as 60/80N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in | 3600.00 | Sqm | 443.70 | 1597320.00 | INR Fifteen Lakh Ninety Seven Thousand Three Hundred & Twenty Only |
| 24 | Grading roof for water proofing treatment with Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) | 75.00 | Cum | 6616.35 | 496226.25 | INR Four Lakh Ninety Six Thousand Two Hundred & Twenty Six and Paise Twenty Five Only |
| 25 | Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid door/window/Clerestory Ywindows & other Frames/Chowkhat comprising of virgin PVC polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) fabricated with miter joints after applying PVC solvent cement and screwed with full body threaded star headed SS screws having minimum frame density of 750 kg/cum, screw withdrawal strength of 2200 N (Face) & 1100 N (Edge), minimum compressive strength of 58 N/mm2, modulus of elasticity 900 N/mm2 and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof | 119.70 | metre | 851.55 | 101930.54 | INR One Lakh One Thousand Nine Hundred & Thirty and Paise Fifty Four Only |

| | | | | | | |
|----|---|--------|-----|----------|------------|--|
| 26 | Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid decorative type flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/ mm2, modulus of elasticity 850 N/mm2 and resistance to spread of flame of Class A category with property of being termite/ borer proof, water/moisture proof and fire retardant. WPC to be laminated with PVC foil of minimum 14 microns thick of approved design pasted with hot melt adhesive on both faces of shutter and fixing | 55.35 | sqm | 3,729.40 | 206422.29 | INR Two Lakh Six Thousand Four Hundred & Twenty Two and Paise Twenty Nine Only |
| 27 | Providing and fixing PVC false ceiling with all fitting and fixtures as per Instruction of EIC. | 582.01 | sqm | 1231.27 | 716611.45 | INR Seven Lakh Sixteen Thousand Six Hundred & Eleven and Paise Forty Five Only |
| 28 | Providing and fixing PVC wall panel with all fitting and fixtures as per Instruction of EIC. | 855.74 | sqm | 1349.92 | 1155180.54 | INR Eleven Lakh Fifty Five Thousand One Hundred & Eighty and Paise Fifty Four Only |
| 29 | supplying and installation of ACP cladding over walls with all necessary materials ,fittings and fixture complete as per instruction of EIC | 399.00 | sqm | 3884.15 | 1549775.85 | INR Fifteen Lakh Forty Nine Thousand Seven Hundred & Seventy Five and Paise Eighty Five Only |
| 30 | Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). | 150.00 | kg | 514.30 | 77145.00 | INR Seventy Seven Thousand One Hundred & Forty Five Only |

| | | | | | | |
|----|---|---------|---------------------|-----------|-----------|--|
| 31 | Provisioning and commissioning of acrylic board of thickness 2.00 mm or more and 4.00 mm thick ACP cover at back, with LED light inside of required colour, MS pipe to hold the board, Labour and equipments for fitting, wire required upto 1.00 meter as per instructions of EIC. The rate also includes 03.00 years of warranty from the date of commissioning. (Note : The measurement shall be done for front elevation part only without deducting gaps if any or so.) | 96.84 | sqft | ₹2,208.00 | 213822.72 | INR Two Lakh Thirteen Thousand Eight Hundred & Twenty Two and Paise Seventy Two Only |
| 32 | Providing steel letters and symbols over the front wall having granite facing as per EIC. | 2000.00 | per letter per inch | 46.50 | 93000.00 | INR Ninety Three Thousand Only |
| 33 | Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills , facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels13:10Area of slab over 0.50 sqm | 120.00 | Sqm | 3701.15 | 444138.00 | INR Four Lakh Forty Four Thousand One Hundred & Thirty Eight Only |
| 34 | Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. | 7504.84 | sqm | 15.25 | 114448.81 | INR One Lakh Fourteen Thousand Four Hundred & Forty Eight and Paise Eighty One Only |
| 35 | Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. | 7504.84 | Sqm | 89.25 | 669806.97 | INR Six Lakh Sixty Nine Thousand Eight Hundred & Six and Paise Ninety Seven Only |

| | | | | | | |
|----|--|---------|-----|--------|-----------|--|
| 36 | Providing & Applying high quality acrylic modified resin based texture of Dholpur/Red sand stone Pattern with anti algae and UV resistance properties to be applied as intermediate finish in desired pattern @ 43.04 kgs/10 sqm to form film of 1- 1.5 mm thickness after scrapping and properly cleaning the surface to remove loose particles from the plaster surface, followed by top coating with Premium Acrylic Smooth exterior paint with Silicone additives of required shade by two or more coats @ 1.43 litres/10 sqm, complete as the direction of Engineer -in-Charge. | 1566.76 | Sqm | 396.60 | 621377.02 | INR Six Lakh Twenty One Thousand Three Hundred & Seventy Seven and Paise Two Only |
| 37 | Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work | 1733.69 | sqm | 65.65 | 113816.75 | INR One Lakh Thirteen Thousand Eight Hundred & Sixteen and Paise Seventy Five Only |
| 38 | Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS : 1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing and panelling to be paid for separately): For fixed portion. Powder | 522.76 | Kg | 395.15 | 206568.61 | INR Two Lakh Six Thousand Five Hundred & Sixty Eight and Paise Sixty One Only |

| | | | | | | |
|----|--|--------|-----|---------|-----------|---|
| 39 | Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS : 1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing and panelling to be paid for separately): For fixed portion. Powder | 408.48 | Kg | 462.05 | 188738.18 | INR One Lakh Eighty Eight Thousand Seven Hundred & Thirty Eight and Paise Eighteen Only |
| 40 | Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):With float glass panes of 4 mm thickness | 103.44 | Sqm | 1090.10 | 112759.94 | INR One Lakh Twelve Thousand Seven Hundred & Fifty Nine and Paise Ninety Four Only |
| 41 | Providing and fixing 12mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS:12823 Gradel Type II,in panelling fixed in aluminum doors, windows shutters and partition frames with C.P.brass/stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge.Pre-laminated particle board with decorative lamination on both sides | 179.20 | sqm | 789.7 | 141514.24 | INR One Lakh Forty One Thousand Five Hundred & Fourteen and Paise Twenty Four Only |
| 42 | Renewing glass panes, with putty and nails wherever necessary:Float glass panes of thickness 4 mm | 20.00 | sqm | 757.1 | 15142.00 | INR Fifteen Thousand One Hundred & Forty Two Only |

| | | | | | | |
|----|---|--------|-------|--------|----------|--|
| 43 | Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes: 110 mm diameter | 288.00 | metre | 262.40 | 75571.20 | INR Seventy Five Thousand Five Hundred & Seventy One and Paise Twenty Only |
| 44 | Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. 110 mm bend | 160.00 | each | 114.60 | 18336.00 | INR Eighteen Thousand Three Hundred & Thirty Six Only |
| 45 | Providing and fixing unplasticised -PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc. complete: 110 mm each | 240.00 | each | 234.80 | 56352.00 | INR Fifty Six Thousand Three Hundred & Fifty Two Only |
| 46 | Providing and fixing chromium plated brass butt hinges with necessary screws etc. complete. 100x70x4 mm (ordinary type) | 280.00 | each | 126 | 35280.00 | INR Thirty Five Thousand Two Hundred & Eighty Only |
| 47 | Providing and fixing chromium plated brass handles with necessary screws etc. complete:125 mm | 200.00 | each | 196.25 | 39250.00 | INR Thirty Nine Thousand Two Hundred & Fifty Only |
| 48 | Providing and fixing chromium plated brass handles with necessary screws etc. complete:100 mm | 200.00 | each | 172.6 | 34520.00 | INR Thirty Four Thousand Five Hundred & Twenty Only |
| 49 | Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete :200x10 mm | 110.00 | each | 51.8 | 5698.00 | INR Five Thousand Six Hundred & Ninety Eight Only |
| 50 | Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete :300x16 mm. | 25.00 | each | 153.75 | 3843.75 | INR Three Thousand Eight Hundred & Forty Three and Paise Seventy Five Only |

| | | | | | | |
|----|--|-------|------|---------|----------|---|
| 51 | Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require : White Vitreous China Flat back wash basin size 550x400 mm with single 15 mm C.P. brass pillar tap. | 20.00 | each | 1458.10 | 29162.00 | INR Twenty Nine Thousand One Hundred & Sixty Two Only |
| 52 | Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings. | 20.00 | each | 1302.20 | 26044.00 | INR Twenty Six Thousand & Forty Four Only |
| 53 | Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. | 20.00 | each | 1126.55 | 22531.00 | INR Twenty Two Thousand Five Hundred & Thirty One Only |
| 54 | Providing and fixing PTMT towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved quality and colour, weighing not less than 88 gms. | 20.00 | Nos | 177.7 | 3554.00 | INR Three Thousand Five Hundred & Fifty Four Only |
| 55 | Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : White Vitreous china Orissa pattern W.C. pan of size 580x440mm with integral type foot rests. | 16.00 | each | 4774.45 | 76391.20 | INR Seventy Six Thousand Three Hundred & Ninety One and Paise Twenty Only |
| 56 | Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : W.C pan with ISI marked white solid plastic seat and lid | 10.00 | No | 4565.40 | 45654.00 | INR Forty Five Thousand Six Hundred & Fifty Four Only |

| | | | | | | |
|----|--|---------|------|----------|-----------|--|
| 57 | Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15cm deep and disposal of rubbish, lead upto 50m and lift up to 1.5 m. All kind of soil | 2000.00 | sqm | 19.75 | 39500.00 | INR Thirty Nine Thousand Five Hundred Only |
| 58 | Providing and fixing CP brass bib cock of approved quality as per instruction of EIC: 15mm | 50.00 | each | 376.95 | 18847.50 | INR Eighteen Thousand Eight Hundred & Forty Seven and Paise Fifty Only |
| 59 | Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS: 8931: 15 mm nominal bore | 50.00 | No | 516.35 | 25817.50 | INR Twenty Five Thousand Eight Hundred & Seventeen and Paise Fifty Only |
| 60 | Providing and fixing double action hydraulic floor spring of approved brand and manufacture IS : 6315 marked, for doors including cost of cutting floors as required, embedding in floors and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charges. With stainless steel cover plate | 5.00 | no.s | 2,086.30 | 10431.50 | INR Ten Thousand Four Hundred & Thirty One and Paise Fifty Only |
| 61 | Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete. | 50.00 | Nos | 731.30 | 36565.00 | INR Thirty Six Thousand Five Hundred & Sixty Five Only |
| 62 | Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rail of T-iron 40x40x6mm with 40mm dia, steel pulleys complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer. | 49.14 | sqm | 7450.80 | 366132.31 | INR Three Lakh Sixty Six Thousand One Hundred & Thirty Two and Paise Thirty One Only |

| | | | | | | |
|----|---|---------|------|-----------|-----------|--|
| 63 | Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing and cleaning etc. complete on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand).Dark shade using ordinary Cement | 664.48 | sqm | 792.95 | 526899.42 | INR Five Lakh Twenty Six Thousand Eight Hundred & Ninety Nine and Paise Forty Two Only |
| 64 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) | 52.88 | cum | ₹6,490.90 | 343238.79 | INR Three Lakh Forty Three Thousand Two Hundred & Thirty Eight and Paise Seventy Nine Only |
| 65 | Supplying labours, tools and tackles for cleaning filled and choaked man hole, septic tank, inspection-chamber, gullay pits, sewerage tank etc. in all lift and disposal of spoils upto a lead of 50M all complete as per specification and direction of Engineer-in-charge. | 75.10 | cum | 1204.2 | 90435.42 | INR Ninety Thousand Four Hundred & Thirty Five and Paise Forty Two Only |
| 66 | Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level: Cement mortar 1:4 (1 cement :4 coarse sand) | 50.00 | Sqm | 802.35 | 40117.50 | INR Forty Thousand One Hundred & Seventeen and Paise Fifty Only |
| 67 | Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead :Of area upto 3 sq. metres | 80.00 | each | 218.95 | 17516.00 | INR Seventeen Thousand Five Hundred & Sixteen Only |
| 68 | Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead. | 2000.00 | sqm | 32 | 64000.00 | INR Sixty Four Thousand Only |
| 69 | Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metre lead.For thickness of tiles above 25 mm and upto 40 mm | 955.46 | sqm | 67.95 | 64923.51 | INR Sixty Four Thousand Nine Hundred & Twenty Three and Paise Fifty One Only |
| 70 | Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete | 7504.84 | sqm | 98.45 | 738851.50 | INR Seven Lakh Thirty Eight Thousand Eight Hundred & Fifty One and Paise Fifty Only |

| | | | | | | |
|----|--|--------|-------|---------|------------------|--|
| 71 | Carriage of building rubbish including loading, unloading and stacking . Lime moorum building rubbish-5 km lead | 723.13 | Cum | 168.10 | 121558.15 | INR One Lakh Twenty One Thousand Five Hundred & Fifty Eight and Paise Fifteen Only |
| 72 | Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge:In cement mortar | 15.00 | Cum | 1194.45 | 17916.75 | INR Seventeen Thousand Nine Hundred & Sixteen and Paise Seventy Five Only |
| 73 | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer in charge:1:3:6 or richer mix | 58.00 | cum | 1412.40 | 81919.20 | INR Eighty One Thousand Nine Hundred & Nineteen and Paise Twenty Only |
| 74 | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc.15mm | 300.00 | metre | 336.20 | 100860.00 | INR One Lakh Eight Hundred & Sixty Only |
| 75 | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge:25 mm nominal outer dia Pipes | 150.00 | metre | 331.50 | 49725.00 | INR Forty Nine Thousand Seven Hundred & Twenty Five Only |

| | | | | | | |
|----|--|---------|-------|---------|-----------|---|
| 76 | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge:20 mm nominal outer dia Pipes | 150.00 | metre | 259.05 | 38857.50 | INR Thirty Eight Thousand Eight Hundred & Fifty Seven and Paise Fifty Only |
| 77 | Providing and fixing CP brass angle valve of approved quality as per instruction of EIC:15mm | 20.00 | No | 434.40 | 8688.00 | INR Eight Thousand Six Hundred & Eighty Eight Only |
| 78 | Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank | 5000.00 | ltrs | 8.40 | 42000.00 | INR Forty Two Thousand Only |
| 79 | Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared. | 3000.00 | sqm | 10.20 | 30600.00 | INR Thirty Thousand Five Hundred & Ninety Nine and Paise One Hundred Only |
| 80 | Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350mm and 340x410x265mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :One urinal basin with 5 litre white P.V.C. automatic flushing cistern. | 20.00 | Nos | 4257.55 | 85151.00 | INR Eighty Five Thousand One Hundred & Fifty One Only |
| 81 | Providing and Fixing all complete Wood Plastic Composit (WPC) Louvers in on the internal part of building on putty applied wall or ceiling surfaces as per direction of EIC: Thickness 23.00 mm | 1381.16 | sqft | 203.26 | 280734.58 | INR Two Lakh Eighty Thousand Seven Hundred & Thirty Four and Paise Fifty Eight Only |

| | | | | | | |
|-------------------------------|--|----------------------|--------|--------|--------------------|--|
| 82 | Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in-Charge. | 26 | each | 78.25 | 2034.50 | INR Two Thousand &Thirty Four and Paise Fifty Only |
| 83 | Dismantling of flushing cistern of all types (C.I /PVC/Nitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead. | 30.00 | each | 67 | 2010.00 | INR Two Thousand &Ten Only |
| 84 | Dismantling C.I. or asbestos rain water pipe with fittings and clamps including stacking the material within 50 metres lead :100mm dia pipe | 90.00 | metre | 45.25 | 4072.50 | INR Four Thousand &Seventy Two and Paise Fifty Only |
| 85 | Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge. | 10.00 | cum | 2060.5 | 20605.00 | INR Twenty Thousand Six Hundred & Five Only |
| 86 | Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality.1.0mm thick | 287.50 | sqm | 643.15 | 184905.63 | INR One Lakh Eighty Four Thousand Nine Hundred & Five and Paise Sixty Two Only |
| 87 | Finishing walls with water proofing cement paint of required shade : 13.109.1 Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litrs/10 sqm complete including cost of Priming coat. | 672.00 | sqm | 72.3 | 48585.60 | INR Forty Eight Thousand Five Hundred & Eighty Five and Paise Sixty Only |
| 88 | Removal of old tarfelt and disposal of debris with all leads complete as per direction of E/I. | 3600.00 | sqm | 53.85 | 193860.00 | INR One Lakh Ninety Three Thousand Eight Hundred & Sixty Only |
| 89 | Total impact of GST for the purpose of CTC | 1.000 | Nos | 0.00 | 0.00 | INR Zero Only |
| Total in Figures | | | | | 19935646.51 | INR One Crore Ninety Nine Lakh Thirty Five Thousand Six Hundred & Forty Six and Paise Fifty One Only |
| Quoted Rate in Figures | | | Select | | 0.00 | INR Zero Only |
| Quoted Rate in Words | | INR Zero Only | | | | |