

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL

Name of the Work / Contract No:	Laying of two nos. 8 inch dia delivery range and two nos. 10 inch dia delivery range from Jehlitand Sump to Sona Dubha Nallah and dismantling of existing four nos. of delivery range for clearing the dumping Area under KDH OCP, NK Area.	NIT No: (NK)/EnM/eNIT/2025-26/27; Dated: 29.04.2025.			
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Dismantling of 10" dia pipeline	1400	Mtr		0.00	INR Zero Only
2	Dismantling of 8" dia pipeline	2400	Mtr		0.00	INR Zero Only
3	Laying of 10" dia pipeline	5600	Mtr		0.00	INR Zero Only
4	Transportation of 10" dia MS pipeline (Loading and unloading from TMV to work site).	5600	Mtr		0.00	INR Zero Only
5	Laying of 8" dia pipeline	5600	Mtr		0.00	INR Zero Only
6	Transportation of 8" dia MS pipeline (Loading and unloading from TMV to work site).	5600	Mtr		0.00	INR Zero Only
7	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50m. All kind of soil.	1200	Cum		0.00	INR Zero Only
8	Cutting of 10" dia and 8" dia pipeline for suitable welding	803940.48	mm		0.00	INR Zero Only
9	Fixing and making of pipe joint 10" dia pipeline by required welding.	1488247	mm		0.00	INR Zero Only
10	Fixing and making of pipe joint 8" dia pipeline by required welding.	1190597.6	mm		0.00	INR Zero Only
11	Making of 10" dia pipe bend L-type and 120 degree bend as per requirement and fixing of both ends with the help of gas cutting and welding with proper centering	60	Nos		0.00	INR Zero Only
12	Making of 8" dia pipe bend L-type and 120 degree bend as per requirement and fixing of both ends with the help of gas cutting and welding with proper centering	60	Nos		0.00	INR Zero Only
13	Providing and fixing of 10" dia flanges.	60	Nos		0.00	INR Zero Only
14	Providing and fixing of 8" dia flanges.	60	Nos		0.00	INR Zero Only
15	Providing and fixing of Nut-Bolt as per requirement	600	Nos		0.00	INR Zero Only
16	Dismantling of sluice valve and NR Valve and transportation of sluice valve and NR valve from other site to work site.	16	Nos		0.00	INR Zero Only
17	Fixing of sluice valve and NR Valve	16	Nos		0.00	INR Zero Only
18	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				