

Tender Inviting Authority: SOEAM,GM Unit Kuju						
Name of the Work / Contract No:	Rearrangement of power supply with all safety features inst installation and upgradation like shade and foundation, gravelling, interlocking for 01 no. VCB and 01 no. 310KVA, 3.3KV/400V indoor transformer with earth pits construction at Shiv Mandir Colony Substation of Topa OCP under Kuju Area.			NT No.: GM (K)EnM/e-Tender/25-26/17		
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P
1	2	3	4	5	6	7
2	A)-Shade and Foundation with earth pit					
3	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	3.75	cum			0.00 INR Zero Only
4	Brick work with common burnt clay F.P.S. non modular) bricks of class designation 7.5 in foundation and plinth m:Cement mortar 1-4 (1 cement: 4 coarse sand)	5.04	cum			0.00 INR Zero Only
5	Cement plaster skirting up to 30 cm height, with cement mortar 1:3 (1 cement: 3 coarse sand), finished with a floating coat of neat cement. 18 mm thick sqm	11.00	sqm			0.00 INR Zero Only
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:3:6 (1 Cement: 3 coarse sand (zone-III) 6 graded stone aggregate 20 mm nominal size)	3.60	cum			0.00 INR Zero Only
7	Structure steel work riveted bolted or welded in built up section, trusses and framed work, including cutting hoisting, fixing in position and applying a priming coat of approved steel primer all complete	1680.80	kg			0.00 INR Zero Only
8	Providing corrugated G.S. sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required, (0.80 mm thick with zinc coating not less than 275 gm/qr)	172.00	sqm			0.00 INR Zero Only
9	Earthing with copper earth plate 600mm x 600mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.75 metre long etc. with charcoal coke and salt as required (2Nos body earthing for 01 Nos VCB, 2Nos for metal of INos TR. and 1 Nos for body earthing	4.00	nos			0.00 INR Zero Only
10	Supply of 35sqmm single core Flexible Al Cable	80.00	mtr			0.00 INR Zero Only
11	Supply and fixing of 35sqmm Al lug	8.00	nos			0.00 INR Zero Only
12	B)-Leveling and Gravelling					
13	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil. (30mX20mX.24m-144CUM)	144.00	cum			0.00 INR Zero Only
14	Supply, filling, spreading and levelling gravels of size range 5 mm to 20 mm, in the recharge pit, over the existing layer of boulders, in required thickness, for all leads & lifts, all complete as per direction of Engineer in	72.00	cum			0.00 INR Zero Only
15	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete. (30mX20mX. 12m=72CUM)	72.00	cum			0.00 INR Zero Only
16	C) INTERLOCKING					
17	Supply and fixing of L limit switch	2.00	nos			0.00 INR Zero Only
18	Copper cable 2.5 sq.mm x 2 core	40.00	mtr			0.00 INR Zero Only
19	Auxiliary contactor, 110V AC/DC 4 NO+4NC	2.00	nos			0.00 INR Zero Only
20	Erection cost of sl. No. 17 to 19 @ 10%	1.00	L/s			0.00 INR Zero Only
21	Total Impact of GST for the purpose of CTC	1.000	nos		0.00	0.00 INR Zero Only
Total in Figures						0.00 INR Zero Only
Quoted Rate in Words	INR Zero Only					