

Tender Inviting Authority: Project Engineer (E&M), Ashok OCP, Piparwar Area

Name of the Work / Contract No:

(A) Erection of continuous earth conductor in the HT Over head line of various feeders from 5 MVA S/S at Ashok Patch (14.3 km) (B) Erection and Dismantling of HT OH line as and when required basis for production related activity as per requirement of the Mining activity under Ashok OCP, Piparwar Area.

NIT No. : PO(AK)/PE(EnM)/e-NIT/25-26/10

Category of Services (To Be Selected by Department)

Category of Bidder (To Be Selected by Bidder)

To Be Entered by Department

ITC Available

Works Contract

Bidder's Status (Mandatory)

Total GST (in Rs.)

GST to be Paid By Bidder (in Rs.)

GST to be Paid By CIL/Subsidiary (in Rs.)

Name of the Bidder/ Bidding Firm / Company :

Select

18

0.00

0.00

0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (With taxes) in Rs. P	BASIC RATE (Without taxes) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Part-A Erection of continuous earth conductor in the HT Over head the of vanous feeders from 5 MVA SIS at Ashok Patch (14.3 km) Supply of 7/10 size SWG GI wire for earth conductor including binding etc as required (14310 Mir) 0.460KG/mtr	6711	Kg	74.34		0.00	INR Zero Only
2	Erection of 7/10 size SWG GI wire for earth conductor including binding etc. as required (14310 Mir) 0.469KG/mtr	6711	Kg	34.22		0.00	INR Zero Only
3	Earthing with G-1 earth plate 600 mm x600mm X6 mm thick including accessories and 3providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc with charcoal coke and salt as required	34	Nos	7199.18		0.00	INR Zero Only
4	Supplying and laying 25 mm X 5 mm G1 strip at 0.50 metre below ground as strip earth electrode, including connection/terminating with Gi nut bolt	760	Mtr	143.96		0.00	INR Zero Only
5	Part-B Erection and Dismantling of HT OH line as and when required basis for production related activity as per requirement of the Mining activity . Erection of steel tubular or rail pole strut in cement concrete 13.6 (1 cement 3 coarse sand; 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and secured with holding clamps, bolts, nuts etc as required.	46	Nos	7679.44		0.00	INR Zero Only
6	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 18 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle (20 mm X 60 cm), 7/3.15 mm dia GI, stay wire and strain insulator etc in cement concrete 136 (1 cement 3 coarse sand 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc as required	20	Nos	3833.82		0.00	INR Zero Only
7	Erection of double pole 3 wire cross arm for 11KV/22KV/33 KV over head lines as required	14	Set	1092.68		0.00	INR Zero Only
8	Erection of angle iron/ channel iron cross arm 4 on wood/ RCC/PCC/steel tubular/ rail pole etc as renoided	18	Set	265.50		0.00	INR Zero Only
9	Supplying and erection of 11 KV disc insulator for 11 KV over head lines with galvanised 5 insulator fittings, ball and socket type and 42 complete with galvanised strain clamps, bolts nuts, washers etc as required	42	Set	965.24		0.00	INR Zero Only
10	Supplying and erection of 11 KV pin insulator for 11 KV over head lines with galvanised insulator 6 fittings ball and socket type and complete with galvanised strain clamps, bolts, nuts washers etc. as required	108	Set	293.82		0.00	INR Zero Only
11	Erection of all aluminium conductor of 7/1.96 7 mm to 7/3 10mm diameter including binding etc as required (4950 Mir) @ 272KG/KM	1346	kg	224.20		0.00	INR Zero Only
12	Supply of 8 SWG GI wire for earth wire (2090) mtr) and erection and fabrication cradle guard (30 spans) cradling with binding etc. 1650 Mtr) @ 0.469 Kg/mtr 30 span x 21 kg/span	1404	kg	74.34		0.00	INR Zero Only
13	Erection of G.I wire No 8 SWG inluding binding etc as required.	600	Nos	62.54		0.00	INR Zero Only
14	Erection of G.I. Wire No B SWG including binding etc as required	773.9	Kg	34.22		0.00	INR Zero Only
15	Dismantling of pole/ street light standard/strut embedded in cement concrete foundation etc .	40	Nos	2736.42		0.00	INR Zero Only
16	Dismantling of over head lines comprising of copper aluminium over head conductor, GI wire, cross arms, insulators etc as required.	1879	Kg	75.52		0.00	INR Zero Only
17	Total Impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words							INR Zero Only