

Tender Inviting Authority: Project Engineer (E&M), Ashok OCP, Piparwar Area

Name of the Work / Contract No:

Maintenance of various HT OH line (33kv,3.3 kv. 11 mines duing upcoming monsoon under Ashok OCP, Piparwar Area.

NIT No. : PO(AK)/PE(EnM)/e-NIT/25-26/11

Category of Services (To Be Selected by Department)

Category of Bidder (To Be Selected by Bidder)

To Be Entered by Department

ITC Available

Works Contract

Bidder's Status (Mandatory)

Total GST(In Rs.)

GST to be Paid By Bidder (in Rs.)

GST to be Paid By CIL/Subsidiary (in Rs.)

Name of the Bidder/ Bidding Firm / Company :

Select

18

0.00

0.00

0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (With taxes) in Rs. P	BASIC RATE (Without taxes) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Erection of metallic pole (above 10 mtr and upto 12 mtr) in cement concrete 1:3:6 (1 cement: 3 coarse sand; 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and secured with holding clamps, bolts, nuts, etc as required.	20	Nos	7424.56		0.00	INR Zero Only
2	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, tum buckle (20 mm X 60 cm), 7/ 3.15 mm dia G.I stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement: 3 coarse sand 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc as required.	25	Nos	3833.82		0.00	INR Zero Only
3	Erection of pole top/ straight two wire/ V shape two 4 wire, angle iron/ channel iron, cross arm on steel 8 tubular/ rail/ PCC pole for 11/22/33 KV as required.	8	Set	482.62		0.00	INR Zero Only
4	Supplying and erection of 11 KV disc insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc, as required.	15	set	965.24		0.00	INR Zero Only
5	Supplying and erection of 11 KV pin insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required	30	Set	293.82		0.00	INR Zero Only
6	Erection of all aluminium conductor of 7/1.96 mm to 7/3.10mm diameter including binding etc required: (40 span 6600 mtr) @ 272KG/KM	1795	Kg	224.20		0.00	INR Zero Only
7	Supply of B SWG: Gf wire for erection and fabrication cradle guard, cradling with binding etc and for 7/10 Galvanized stay wire for earth wire 25 span, 1375 mb 469 kg/km	645	Kg	74.34		0.00	INR Zero Only
8	Earthing with Gil earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc with charcoal coke and salt as required	10	Nos.	7199.18		0.00	INR Zero Only
9	Erection of ring type guard for 25 spans (20 nings/span)	500	Nos.	62.54		0.00	INR Zero Only
10	Supplying and erection of three piece nonlinear resistor type lightning arrestor suitable for 3 wire, 11 KV overhead lines with rated voltage 9 KV (rms) with a nominal discharge current rating of 5 KA, and complete with galvanised clamping arrangement, Gi bolts, nuts, washers etc. as required	15	Set	17.70		0.00	INR Zero Only
11	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					