

ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	(1) Repairing of (A). 325KW, 3.3KV DOL starter SI. No. SA-1619 of GVP Phase-II OCP Providing of Ampere meter	1.00	No.			0.00	INR Zero Only
1.02	Providing of Push button	4.00	Nos.			0.00	INR Zero Only
1.03	Providing of Indication lamp	3.00	Nos.			0.00	INR Zero Only
1.04	Providing of Outgoing Bushing 3.3KV	3.00	Nos.			0.00	INR Zero Only
1.05	Providing of Potential Transformer 3.3KV/110/220 V	1.00	No.			0.00	INR Zero Only
1.06	Providing of Isolator set	1.00	No.			0.00	INR Zero Only
1.07	Providing of CBCT	1.00	No.			0.00	INR Zero Only
1.08	Providing of MPR Protection relay	1.00	No.			0.00	INR Zero Only
1.09	(B). 240KW, 3.3KV DOL starter SI. No. SA-1617 of RKB Pump of GVP Phase-II OCP. Providing of Voltmeter	1.00	No.			0.00	INR Zero Only
1.10	Providing of push button	4.00	Nos.			0.00	INR Zero Only
1.11	Providing of PT Fuse 3.3 KV Grade	2.00	Nos.			0.00	INR Zero Only
1.12	Providing of Earth Leakage relay (Prayog)	1.00	No.			0.00	INR Zero Only
1.13	Providng of ferruel and lugs	1.00	No.			0.00	INR Zero Only
1.14	Providing of Insulator (Outgoing Side)	3.00	Nos.			0.00	INR Zero Only
1.15	Providing of Overload relay	1.00	No.			0.00	INR Zero Only
1.16	Providing of CBCT	1.00	No.			0.00	INR Zero Only
1.17	Providing of MPR Protection relay	1.00	No.			0.00	INR Zero Only
1.18	Providing of Potential Transformer 3.3KV/110/220V	1.00	No.			0.00	INR Zero Only
1.19	(C). 200 KW, 3.3KV DOL starter make Prabhu SI. No. HT582 of GVP Phase-II OCP Providing of Voltmeter	1.00	No.			0.00	INR Zero Only
1.20	Providing of Ampere meter	1.00	No.			0.00	INR Zero Only
1.21	Providing of push button	3.00	Nos.			0.00	INR Zero Only

1.22	Providing of PT Fuse 3.3 Kv Grade	2.00	Nos.			0.00	INR Zero Only
1.23	Providing of Earth Leakage relay (Prayog)	1.00	No.			0.00	INR Zero Only
1.24	Providng of ferruel and lugs	1.00	No.			0.00	INR Zero Only
1.25	Providing of Insulator (Outgoing Side)	2.00	Nos.			0.00	INR Zero Only
1.26	Providing of Potential Transformer 3.3Kv/110/220 V	1.00	No.			0.00	INR Zero Only
1.27	Providing of Overload relay	1.00	No.			0.00	INR Zero Only
1.28	Providing of CBCT	1.00	No.			0.00	INR Zero Only
1.29	Providing of MPR Protection relay	1.00	No.			0.00	INR Zero Only
1.30	(D). 180KW, 3.3KV DOL starter make Teknik Pvt. Ltd., Sl.No SAHD-2711 for Monsoon Preparation 2025-26 of GVP Phase-II QCP. Providing of Ampere meter	1.00	No.			0.00	INR Zero Only
1.31	Providing of Voltmeter	1.00	No.			0.00	INR Zero Only
1.32	Providing of Push button	2.00	Nos.			0.00	INR Zero Only
1.33	Providing of Outgoing Bushing 3.3KV	3.00	Nos.			0.00	INR Zero Only
1.34	Providing of PT Fuse 3.3 Kv Grade	2.00	Nos.			0.00	INR Zero Only
1.35	Providing of Earth Leakage relay (Prayog)	1.00	No.			0.00	INR Zero Only
1.36	Providng of ferruel and lugs	1.00	No.			0.00	INR Zero Only
1.37	Providing of Insulator (Outgoing Side)	2.00	Nos.			0.00	INR Zero Only
1.38	Providing of Overload relay	1.00	No.			0.00	INR Zero Only
1.39	Providing of Isolator set	1.00	No.			0.00	INR Zero Only
1.40	Providing of CBCT	1.00	No.			0.00	INR Zero Only
1.41	Providing of MPR Protection relay	1.00	No.			0.00	INR Zero Only
1.42	Providing of MPR Protection relay	1.00	No.			0.00	INR Zero Only
1.43	(2). Erection of chemical earth pits and supply & installation of On load/online GOAB isolator switch 11KV grade, 630A for Monsoon Preparation 2025 of GVP Phase-II QCP. Making of chemical earthpit resistance value less than 01 Ω at different locations as per direction of Engineer incharge or his representatives for safe earthing electrode having 02 custom made G.I tubes (Glavanised 80 Micro minimum one inside the other of length 03 mtrs. O/D 80mm filled with conductor riched crystalline misture (CCM)	3.00	Sets			0.00	INR Zero Only
1.44	Making of chemical earthpit resistance value less than 01ohm at different locations as per direction of Engineer incharge or his representative for Back fill compound bag of 03x 25kg for each earth pit	3.00	Sets			0.00	INR Zero Only
1.45	On load/online GOAB isolator switch 11KV grade 630 Amp rating capacity	1.00	Set			0.00	INR Zero Only
1.46	Providing of brick work (in width 225mm or more) with FPS bricks of class designated 7.5 in cement mortar 1:4(1 Cement :4 coarse sand) at all levels (0.08 Cu /each X 3 set=0.24 Cum)	0.24	Cu.M			0.00	INR Zero Only

1.47	Supplying and laying 6 SWG G.I. wire at 0.50 metre below ground level for conductor earth electrode, including connection/termination with GI thimble etc. as required.	75.00	Mtrs.			0.00	INR Zero Only
1.48	Installation/labour charges for item sl. No. 1.43, 1.44 & 1.45	1.00	L.S			0.00	INR Zero Only
2	Total impact of GST for the purpose of CTC	1	No.		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					