

| | | | | | | |
|--|--|---------------|--|---|---|-----------------------|
| Tender Inviting Authority: PROJECT OFFICER, RRS, DAKRA, NK AREA, CCL | | | | | | |
| Name of the Work/ Contract No: Repairing and reconditioning of main control panel of Machine Shop (Panel 1 and 2) for controlling power of EOT Crane, Lathe Machine and repairing of Heating Chamber panel and re arrange power for welding generator of Electrical Shop at Regional Repair Shop (NK) Dakra, under GM Unit, NK Area | | | NTT No: PO/RRS/NK/e-NTT/2025-26/02 | | Dr. 10.05.2025 | |
| . | Category of Services (To Be Selected by Department) | | Category of Bidder (To Be Selected by Bidder) | | | |
| TTC Available | | | Works Contract | Bidder's Status (Mandatory) | Total GST(in Rs.) GST to be Paid By Bidder (in Rs.) GST to be Paid By CIL/Subsidiary (in Rs.) | |
| Name of the Bidder/ Bidding Firm/ Company : | | | Select | 0.00 | 0.00 0.00 | |
| PRICE SCHEDULE | | | | | | |
| (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) | | | | | | |
| NUMBER # | TEXT # | NUMBER # | TEXT # | NUMBER # | NUMBER # | TEXT # |
| Sl. No. | Item Description | Quantity | Units | BASIC RATE In Figures To be entered by the Bidder in Rs. P | TOTAL AMOUNT Without Taxes in Rs. P | TOTAL AMOUNT In Words |
| 1 | 2 | 3 | 4 | 6 | 7 | 8 |
| 1 | Laying of one number additional PVC insulated and PVC sheathed! XLPE power cable of 1.1 KV grade of following size direct in ground in the same trench in one tier horizontal formation including excavation, sand cushioning, protective covering and refilling the trench etc. as required. Upto 35 sq. mm | 20 | Meter | | 0.00 | INR Zero Only |
| 2 | Providing of 400A Analog panel ampere meter. | 3 | Set | | 0.00 | INR Zero Only |
| 3 | Providing of 600V screw mounted voltage analog panel volt meter. | 3 | Set | | 0.00 | INR Zero Only |
| 4 | Providing of R.Y.B indicator. | 3 | Set | | 0.00 | INR Zero Only |
| 5 | Providing of cooper lugs 70 Sqmm. | 12 | Nos. | | 0.00 | INR Zero Only |
| 6 | Providing of cooper lugs 120 Sqmm. | 6 | Nos. | | 0.00 | INR Zero Only |
| 7 | Testing, commissioning, Complete cleaning, painting & numbering with name plate of main control panel. | 3 | Set | | 0.00 | INR Zero Only |
| 8 | Providing of 10A Rotary switch mounting on panel. | 6 | Nos. | | 0.00 | INR Zero Only |
| 9 | Providing of 63Amp. C- Curve three pole & neutral MCB. | 17 | Nos. | | 0.00 | INR Zero Only |
| 10 | Providing of 25Sq.mm 3.5 core copper cable. | 20 | Meter | | 0.00 | INR Zero Only |
| 11 | Labour cost @15% on item no. 2 to 10. | 1 | Job | | 0.00 | INR Zero Only |
| 12 | Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire | 70 | Meter | | 0.00 | INR Zero Only |
| 13 | Providing and fixing of 400Amp rating & braking capacity MCCB with thermo magnetic released and terminal spreaders in existing cubical panel board including drilling holes in cubical panel, making connections etc. as required. | 1 | Nos. | | 0.00 | INR Zero Only |
| 14 | Providing and fixing of 250 A rating & braking capacity MCCB with thermo magnetic released and terminal spreaders in existing cubical panel board including drilling holes in cubical panel, making connections etc. as required. | 1 | Nos. | | 0.00 | INR Zero Only |
| 15 | Providing and fixing of 200 A rating & braking capacity MCCB with thermo magnetic released and terminal spreaders in existing cubical panel board including drilling holes in cubical panel, making connections etc. as required. | 1 | Nos. | | 0.00 | INR Zero Only |
| 16 | Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X 10 sq. mm + 1 X 6 sq. mm earth wire | 50 | Meter | | 0.00 | INR Zero Only |
| 17 | Earthing with copper earth plate 600mm x 600mm x 3mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal/ coke and salt as required. | 3 | Set | | 0.00 | INR Zero Only |
| 18 | Total impact of GST for the purpose of CTC | 1 | Nos. | | 0.00 | INR Zero Only |
| Total in Figures | | | | | 0.00 | INR Zero Only |
| Quoted Rate in Words | | INR Zero Only | | | | |