

Tender Inviting Authority: Staff officer (E&M), Amrapali- Chandragupta Area, CCL						
Name of the Work / Contract No:	Dismantling, shifting and laying of pipeline of 6" dia ( 800M approx.) as per requirement with priming arrangement and replacement of different types of damaged valves in existing pipelines at Amrapali OCP under A-C Area			NIT No: G.M.(A-C)/S.O.(E&M)/e-NIT/25-26/05 ; Dated: 12.05.2025		
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00	
<p align="center"><b>PRICE SCHEDULE</b></p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )</p>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Carriage of 150 mm dia. Lead 5 Kms RCC pipe, A.C. pipes, Steel cylinder, R.C. pipes, S.C.I pipes and unreinforced cement pipes	800.000	Mtrs.		0.00	INR Zero Only
2	Laying in postion centrifugally cast (spun) iron S&S or flanged pipes (excluding cost of pipe). ( 800 Mtr. X 28.26 Kg/m= 226.08 Quintal)	226.080	Quintal		0.00	INR Zero Only
3	Providing and fixing bolts including nuts and washers complete	120.00	Kg.		0.00	INR Zero Only
4	welding by gas or electric plant including transportation of plant at site etc. as complete.	9336.00	CM		0.00	INR Zero Only
5	Providing installation testing and commissioning of non-return valve of following sizes confirming to IS: 5312 complete with rubber gasket, GI bolt, nuts, washers etc. As required: 150mm	1.00	Set		0.00	INR Zero Only
6	Providing laying testing & commissioning of 'B' class medium duty G.I. pipe conforming to IS:1239 including welding, fittings like elbows tees, flasnge, tapers, nuts, bolts gasket set and fixing the pipe on wall/ ceiling with suitable clamp/ support frame and paining with two or moe coats of syntheic enamel paint of required shade complete as required. 25mm dia	6.00	Mtrs.		0.00	INR Zero Only

7	BUTTERFLY VALVE ( MANUAL) with CI body SS Disc, nitrile rubber seal & C- ring PN 16 pressure rating for chilled water/ hot eater circulation as specified 40mm	2.00	Each		0.00	INR Zero Only
8	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5m in width as well as 10 sq.mm on plan including getting out and disposal of excavated earth up to 50m and lift upto 1.5m, as directed by Engineer-In charge. (0.3 X 0.5 X 800) M + for dismantling ( 0.5 X 0.5 X 800) M	320.00	Sq.M		0.00	INR Zero Only
9	Providing of 6" dia heavy duty cast iron foot valve	2.00	Each		0.00	INR Zero Only
10	Providing of 6" dia flange ( to replace damaged)	30.00	Each		0.00	INR Zero Only
11	<b>Total impact of GST for the purpose of CTC</b>	1.000	Job	0.00	0.00	INR Zero Only
<b>Total in Figures</b>					0.00	INR Zero Only
<b>Quoted Rate in Words</b>		<b>INR Zero Only</b>				