

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL

Name of the Work / Contract No:	Installation of 750kVA, 3.3kV/440V Trans-switch Unit with fabrication of shed and foundation at Elecon and IR Feeder Breaker under KDH Project, NK Area	NIT No. GM (NK)/EnM/eNIT/2025-26/36; dated 12.05.2025.			
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Providing and installation of chemical type earth pit electrode dia 50mm x 3000 mm along with three bags of back fill compount.	10.00	Set		0.00	INR Zero Only
2	Providing and fixing of 25 mm x 5 mm G.I strip on surface or in recess for connection as required.	100.00	Mtr		0.00	INR Zero Only
3	Supplying and making outdoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for following size of 3 core, XLPE aluminium conductor cable of 11 KV grade as required. 120 Sqmm	4.00	Nos		0.00	INR Zero Only
4	Supplying and making indoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for following size of 3 core, XLPE aluminium conductor cable of 11 KV grade as required. 120 Sqmm	4.00	Nos		0.00	INR Zero Only
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1374.40	kg		0.00	INR Zero Only

6	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-In-charge) 0.50 mm (+0.05%) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/ self tapping screws of size (5.5 x 55 mm) with EPDM seal, complete up to any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	60.00	cum		0.00	INR Zero Only
7	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50m. All kind of soil.	28.00	cum		0.00	INR Zero Only
8	Filling the earth work and brick wall and bring the floor to level suitable for PCC work for base	2.00	Nos		0.00	INR Zero Only
9	Brick on edge flooring with bricks of class designation 7.5 on a bed of 12 mm cement mortar, including filling the joints with same mortar, with common burnt clay non modular bricks 1:6 (1 cement: 6 coarse sand)	56.00	sqm		0.00	INR Zero Only
10	Brick work with FPS bricks of class designation 5 in foundation and plinth in Cement Mortar 1:6 (1 Cement : 6 Coarse sand)	10.50	cum		0.00	INR Zero Only
11	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 cement: 4 coarse sand (zone-III) derived from natural sources: 8 graded stone aggregate 40 mm nominal size derived from natural sources).	5.60	cum		0.00	INR Zero Only
12	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				