

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Staff Officer (EnM), Barka-Sayal Area, CCL.						
Name of the Work / Contract No:	Shifting of submain wiring of Dav school Barkakana and repairing/re-wiring of 05 nos. of quarters at NTS colony Barkakana.					
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
SL. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Wiring for light point / fan point / exhaust fan point / call bell point with 1.5 sq mm FR PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit. With piano type switch, phenolic laminated sheet, suitable size M.S. Box and earthing the point with 1.5 sq mm FR PVC insulated copper conductor single core cable etc as required. Group'A'	87	NO		0.00	INR Zero Only
2	Supplying and fixing following piano switch/socket on the existing switch box/cover including connection etc. as required.(a) 5/6 Amp switch	19	no		0.00	INR Zero Only
3	Supplying and fixing following piano switch/socket on the existing switch box/cover including connection etc. as required.(b) 3 pin 5/6 Amp socket outlet.	19	no		0.00	INR Zero Only
4	Supplying and fixing metal box of 150 mm x 75 mm x 60 mm deep (nominal size) on surface of in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5/6 Amp socket outlet and 5/6 Amp piano type switch connection painting etc. as required.	17	no		0.00	INR Zero Only
5	Supplying and fixing metal box of 180 mm x 100 mm x 60 mm deep (nominal size) on surface of in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 6 pin 5/6 & 15/16 Amp socket outlet and 15/16 Amp piano type switch connection painting etc. as required.	12	no		0.00	INR Zero Only
6	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulator copper conductor, single core cable in surface / recessed medium class PVC conduit as required. (a) 2 x 2.5sq mm + 1 x 2.5 mm earth wire	290	mtr.		0.00	INR Zero Only

7	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulator copper conductor, single core cable in surface / recessed medium class PVC conduit as required.2 x 4 sq mm + 1 x 4 mm earth wire	160	mtr.		0.00	INR Zero Only
8	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in existing surface / recessed steel / PVC conduit as required. 2 x 6 sq.mm	200	mtr.		0.00	INR Zero Only
9	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	14	no		0.00	INR Zero Only
10	Supplying and fixing following way , single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface / recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painting including earthing etc. as required. (but without MCB/RCCB/Isolator) 8 way , double door	5	no		0.00	INR Zero Only
11	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following pole in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	24	nos		0.00	INR Zero Only
12	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following pole in the existing MCB DB complete with connections, testing and commissioning etc. as required. Double pole	5	no		0.00	INR Zero Only
13	Providing and fixing of switch fuse unit/isolator(32A)	5	no		0.00	INR Zero Only
14	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc as required.(a) 200mm x 150mm x 75mm deep	10	nos.		0.00	INR Zero Only
15	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc as required(b) 200mm x 250mm x 60mm deep	10	no		0.00	INR Zero Only
16	Supplying and fixing 3 pin, 5 A ceiling rose on the existing junction Box / wooden block including connection etc. as required.	43	no		0.00	INR Zero Only
17	Supplying and fixing brass batten / angle holder including connection etc. as required	44	no		0.00	INR Zero Only
18	Providing and fixing 6 SWG dia G.I wire on surface or in recess for loop earthing as required.	150	mtr.		0.00	INR Zero Only
19	Chemical Earthing : 80 mm dia Earthing Electrode 3mtr. Length. Backfill Compound chemical 4 Bag (per bag 25 Kg), Earth cutting removing and installation charge.	12	no		0.00	INR Zero Only
20	Providing and fixing off lightning conductor finial,made of 25 mm dia 300mm long,G.I.tube,having single prong at top,with 85 mm dia 6mm thickG.I. base plate including holes etc. complete as required.	5	no		0.00	INR Zero Only
21	Supply of 3.5 core x 50Sq.MM Armoured cable	65	mtr.		0.00	INR Zero Only
22	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulator copper conductor, single core cable in surface / recessed medium class PVC conduit as required.2 x 10sq mm + 1 x 6 sqmm earth wire	120	mtr.		0.00	INR Zero Only
23	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulator copper conductor, single core cable in surface / recessed medium class PVC conduit as required.4 x 10 sq mm + 2 x 6 sqmm earth wire	40	mtr.		0.00	INR Zero Only

24	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulator copper conductor, single core cable in surface / recessed medium class PVC conduit as required.4 X 16 sqmm + 2 X 6 sqmm earth Wire	40	mtr.		0.00	INR Zero Only
25	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. Above 35 sq. mm and upto 95 sq. mm Metre	120	mtr.		0.00	INR Zero Only
26	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required. Above 35 sq. mm and upto 95 sqmm (clamped with 25x3mm MS Flat Clamp)	60	mtr.		0.00	INR Zero Only
27	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.312 X 95 sq. mm (45mm)	4	no		0.00	INR Zero Only
28	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.3% X 50 sq. mm (35mm)	8	no		0.00	INR Zero Only
29	Dismantling and erection of 3.5 Core X 95 sqmm Cable , DB, Main Switch, Basbar and Changeover Switch	1	job		0.00	INR Zero Only
30	Total impact of GST for the purpose of CTC	1.000	No.	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				