

Item Rate BoQ

Tender Inviting Authority: Project Engineer (E&M), Tetariakhar OCP

Name of the Work / Contract No: Maintenance and Erection & Dismantling of 440/220 Volt Lighting Overhead (OH) Line Before Monsoon for Proper Maintenance of Critical Location LT Overhead Lines under Tetariakhar OCP, Rajkara Area.

	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement :3 coarse sand :6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc as required above 8 metre and upto 11 metre .	10	Nos.			0.00	INR Zero Only
2	Supplying and erection of stay set complete (galvanised) with 19/20 mm x 1.8 metres long stay rod, anchor plate of size 450mm x 450mm x 7.5mm, thumbie, stay clamps, bow tightener, 7/4 mm dia G.I stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement :3 coarse sand:6 grade stine aggregate 40 mm nominal size) foundation including excavation and refilling etc.	10	Nos.			0.00	INR Zero Only
3	Supplying of channel iron 75 mm x 40 mm x6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps ,nuts and washers etc including of holes for insulator point bolts ,nuts and washers etc (as per drawing) and painting with primer and finish paints as required.	10	Nos.			0.00	INR Zero Only
4	Erection of all aluminium conductor of 7/8.40mm to 7/8.00 mm diameter and above including binding etc as required 60span x4wire x including binding etc. as required	150	Kg			0.00	INR Zero Only
5	Erection of angle iron /channel iron cross arm on wood /rcz/pcc/steel tubular /rail pole etc as required.	10	Set			0.00	INR Zero Only
6	Erection of cradle guard as required.	25	Each			0.00	INR Zero Only
7	Supply & Erection of pin insulator. 440 v	48	Set			0.00	INR Zero Only
8	Erection of G.I wire no.8 SWG including binding etc .as required for earth continuity.	90	Kg			0.00	INR Zero Only
9	Supply & Erection of shackle insulator of size 100mm x110mm with GI bolt, And straps etc as required.	40	Set			0.00	INR Zero Only
10	Dismantling of pole/street light standard /strut embedded in cement concrete foundation etc. as required	7	Each			0.00	INR Zero Only
11	Dismantling of over head lines comprising of copper/aluminium over head conductor G.I wire cross arm, insulators etc as required	90	Kg			0.00	INR Zero Only
12	Total impact of GST for the purpose of CTC	1	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						