

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL

Name of the Work / Contract No:

Erection, extension cum diversion of 6.6kV OHL required for supplying power to 6.6kV rated Excavators DHD 18211 and 18212 for its operation and advancement of working faces at Quarry No. 01 for overburden removal and coal production along with dismantling of 6.6kV OHL from old working face/ patch as and when required at Quarry No. 01 under Purnadih OCP, NK Area

Category of Services (To Be Selected by Department)

Bidder's Status (Mandatory)

Select

Category of Bidder (To Be Selected by Bidder)

NIT No. GM (NK)/EnM/eNIT/2025-26/47; dated 28.05.2025.

Total GST(in Rs.)

0.00

GST to be Paid By Bidder (in Rs.)

0.00

GST to be Paid By CIL/Subsidiary (in Rs.)

0.00

ITC Available

Works Contract

Name of the Bidder/ Bidding Firm / Company :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc as required. Above 11.00 Metre and upto 13.00 Metre.	42.00	Nos		0.00	INR Zero Only
2	Supply and erection of stay set complete (galvanized) with 19/ 20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle (20 mm x 60 cm), 7/ 3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	18.00	Nos		0.00	INR Zero Only
3	Erection of stay set complete (galvanized) in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	15.00	Nos		0.00	INR Zero Only
4	Erection of all aluminum conductor of 7/1.96 mm to 7/3.10 mm diameter and above including binding etc as required.	1941.00	kg		0.00	INR Zero Only
5	Supplying of two lengths of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) double pole cross arm for three wire 6.6kV/11 KV overhead line conductors complete with through bolts and nuts for clamping to the poles, 50 mm X 6 mm MS flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/fittings, bolts and nuts etc and painting with primer and finish paint as required.	2.00	Set		0.00	INR Zero Only
6	Erection of double pole 3 wire cross arm for 6.6kV/11 KV / 22 KV / 33 KV Over head lines as required.	9.00	Nos		0.00	INR Zero Only
7	Supplying of channel iron 75 mm x 40 mm x 6 mm (7.14 kg per metre) V shape cross arm for two wire 6.6kV/11 KV over head line conductor complete with 50 mm x 6 mm flat iron clamps, bolts and nuts including drilling holes for insulator pins, bolts, nuts, washers etc (as per drawing) and painting with primer and finished paint as required.	8.00	Nos		0.00	INR Zero Only
8	Erection of pole top / straight two wire/ V shape two wire, angle iron / channel iron, cross arm on steel tubular/ rail/ PCC pole for 11/22/33 KV as required.	25.00	Set		0.00	INR Zero Only
9	Supplying and erection of 11 KV disc insulator for 6.6kV/11 KV over head lines with galvanized insulator fittings, ball and socket type and complete with galvanized strain clamps, bolts, nuts, washers etc. as required.	24.00	Set		0.00	INR Zero Only
10	Supply and erection of 6.6kV/11 KV pin insulator complete with large steel head G.I pin, nuts, washers etc as required.	28.00	Nos		0.00	INR Zero Only
11	Erection of disc / pin insulator for 11 KV over head lines as required.	40.00	Set		0.00	INR Zero Only
12	Supply of 8 / 6 SWG G.I. wire	311.00	kg		0.00	INR Zero Only
13	Erection of earth conductor as erection of all aluminium conductor of 7/1.96 mm to 7/3.10 mm diameter including binding etc. as required	281.00	kg		0.00	INR Zero Only
14	Erection of cradle Guard as required.	588.00	Nos		0.00	INR Zero Only
15	Dismantling of over head lines comprising of copper / aluminium over head conductor, G.I. wire, cross arms, insulators etc as required	1636.00	kg		0.00	INR Zero Only
16	Dismantling of pole / street light standard / strut embedded in cement concrete foundation etc as required.	28.00	Nos		0.00	INR Zero Only
17	Handling of PVC insulated and PVC sheathed / XLPE power cable of 6.6kV/11kV grade of size 95/120 Sqmm, 50m length in open ground manually as required during Field Switch shifting of 6.6kV rated Shovels at working face as well as during marching of machines from one face to another.	18.00	times		0.00	INR Zero Only
18	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only