

Tender Inviting Authority:	SO(E&M)/ H					
Name of the Work / Contract No:	Erection/Dismantling of 220V mine LT O/H Line conductor, Pole and accessories for day-to-day work at destination free locations in mine over a period of One year, to meet production urgency of PEOCP under Hzb Area					
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Erection of metallic pole of Above 8.0 metre and upto 10.0 metre length in cement concrete 1:3:6 (1 cement: 3 coarse sand:6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc. as required .	50	Nos			0.00	INR Zero Only
2	Supply & erection of stay sets complete (galvanised) with 19/20mm diax1.8m long stay rod, anchor plate of size 45cmx45cmx7.5mm, thimble,stay clamps, bow tightener, 7/3.15 mm dia G.I. stay wire and strain insulator etc. in cement concrete 1:3:6(1 cement:3 coarse sand: 6 graded stone aggregate 40mm nominal size)foundation including excavation and refilling etc. as required.	25	Nos			0.00	INR Zero Only
3	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 2 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required	75	Set			0.00	INR Zero Only
4	Erection of angle iron/channel cross arm on wood/RCC/PCC/Steel tubular/rail pole etc. as required.	100	Set			0.00	INR Zero Only
5	Supply & erection of 100mmx80mm pin insulator complete with G.I spindle and nuts etc. as required.	70	Set			0.00	INR Zero Only
6	Supply & erection of 100mmx110mm shackle insulator with G.I bolt, nuts & straps etc .as required.	30	Set			0.00	INR Zero Only
7	Erection of ACSR conductor of 7/2.11mm to 7/3.00 dia and above including binding etc. as required.	500	Kg			0.00	INR Zero Only
8	Supply of 8 SWG GI Wire for cradling of O/H cross line (for 10 span)(Less GST@18% Rs.87.50-13.35=74.15)	260	Kg			0.00	INR Zero Only
9	Erection of GI wire No.8 SWG including binding etc. as required.	260	Kg			0.00	INR Zero Only
10	Dismantling of O.H line comprising of copper/aluminium O.H conductor GI wire, cross arms, insulators etc. as required.	500	Kg			0.00	INR Zero Only
11	Dismantling of pole/street light standard/strut embedded in cement concrete foundation etc as required.	50	Nos			0.00	INR Zero Only
12	Cost of painting of poles 10M length including channel bracket and cross arm (with one coat red-oxide paint & two coat aluminium paint)	40	Nos			0.00	INR Zero Only
13	Total impact of GST for the purpose of CTC	1.00	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					