

Tender Inviting Authority:	SO(E&M)/ H					
Name of the Work / Contract No:	Fabrication of shed for 1) 125KVA DG Set and 2) 750KVA, 11KV/440V Transformer 3)100KVA, 11KV/440V Transformer and repair of shed of 1MVA, 11KV/440V Transformer, installed at GM Unit, Hazaribagh area					
.	Category of Services ( To Be Selected by Department)	Category of Bidder ( To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Structure steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	466	kg			0.00	INR Zero Only
2	Providing corrugated G S sheet roofing including verticle/curved surface fixed withpolymer coated J or L hooks, bolts and nuts 8 mm dimeter with bitumen and G I limpet washer or with G I limpet washer filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete ( up to any pitch in horizontal/ verticle or curved surfaces), excluding the cost of purlins and trussesand including cutting to size and shape wherever required.	210	Sqm			0.00	INR Zero Only
3	Erection of metallic pole of above 4.5 meter and up to 6.5 meter length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required .( For fencing work)	18	each			0.00	INR Zero Only
4	Providing and making steel pole collar with cement concrete (1 cement: 3 coarse sand : 6 stone aggregate 20mm) of specified size and shape including form work, plastering if required, curing etc as required. (volume of pole/ pipe not to be deducted)	3.5	Cum			0.00	INR Zero Only
5	Painting of shed including labour cost with one coat red oxide 420/6 = 70ltr	70	ltr			0.00	INR Zero Only
6	Painting of shed including labour cost with 2 coat aluminium paint 420x2coat/6 = 140ltr	140	ltr			0.00	INR Zero Only
7	Total impact of GST for the purpose of CTC	1.00	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					