

Tender Inviting Authority:	Project Engineer (EnM), TNOCP, Hazaribagh Area					
Name of the Work / Contract No:	Fresh wiring including safety device in Diesel dispensing unit at TNOCP under Hazaribagh Area.					
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By ClL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder In Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7	8
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.	10	Point			0.00	INR Zero Only
2	Wiring for light/ power plug with 2 X 4 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit along with 1 no. 4 sq. mm modular switch, modular plate, suitable GI box and earthing. FRLS PVC insulated copper conductor single core cable for loop earthing as required.	25	Metre			0.00	INR Zero Only
3	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	2	Each			0.00	INR Zero Only
4	Supplying and fixing 3 pin, 5 amp ceiling rose on the existing junction box/ wooden block including connection etc as required.	6	Each			0.00	INR Zero Only
5	Supplying and fixing brass batten/ angle holder including connection etc. as required.	4	Each			0.00	INR Zero Only
6	Supplying and fixing of modular switch 5/6 amps switch on the existing modular plate & switch box including connections but excluding modular plate etc. as required.	14	Each			0.00	INR Zero Only
7	Supplying and fixing of modular switch 15/16 amps switch on the existing modular plate & switch box including connections but excluding modular plate etc. as required.	4	Each			0.00	INR Zero Only
8	Supplying and fixing of modular socket 3 pin 5/6 amps socket outlet on the existing modular plate & switch box including connections but excluding modular plate etc. as required.	14	Each			0.00	INR Zero Only
9	Supplying and fixing of modular socket 6 pin 15/16 amps socket outlet on the existing modular plate & switch box including connections but excluding modular plate etc. as required.	4	Each			0.00	INR Zero Only
10	Supplying and fixing 12 module (200 mm X 150 mm)size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc.	4	Each			0.00	INR Zero Only
11	Supplying and fixing 25 A rating, double pole, (single phase and neutral), 240 V, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connection, testing and commissioning etc. as required.	5	Each			0.00	INR Zero Only
12	Supplying and fixing 40 A rating, double pole, (single phase and neutral), 240 V, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connection, testing and commissioning etc. as required.	1	Each			0.00	INR Zero Only
13	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7metre long etc. with charcoal/ coke and salt as required.	9	Set			0.00	INR Zero Only
14	Wiring for circuit/ submain wiring alongwith earth wire with 4 X 10 sq. mm + 2 X 6 sq. mm earth wire of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required	60	Metre			0.00	INR Zero Only
15	Supply & fixing 63 Amp, 4 Pole Main Switch	2	No.			0.00	INR Zero Only
16	Supply & fixing 63 Amp, 3 Phase Change Over SwitchMain Switch	1	No.			0.00	INR Zero Only
17	Supply and fixing of 16 sq mm Copper conductor unarmoured cable single core 1100 voltaee grade	135	Mtr.			0.00	INR Zero Only
18	Supply and fixing of 16 sq mm Copper Lug	18	No.			0.00	INR Zero Only
19	Supply and fixing of 10 mm X 25 mm long tinned brass bolt with nut etc.	18	No.			0.00	INR Zero Only
20	Supply and fixing of Lightning conductor	2	No.			0.00	INR Zero Only
21	Supply and fixing of Insulator	2	No.			0.00	INR Zero Only
22	Supply & fixing 20 W LED Tube Light	2	No.			0.00	INR Zero Only
23	Supply & fixing 15 W LED Bulb	4	No.			0.00	INR Zero Only
24	Supply and fixing of 2.5' x 3.5' size wooden Box	1	No.			0.00	INR Zero Only
25	Total impact of GST for the purpose of CTC	1.00	No		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						