

Validate		Print		Help		Percentage BoQ	
Tender Inviting Authority: Staff Officer (Civil),CCL, Dhori Area							
Name of Work:-Laying of pipeline for water supply near GM colony under GM unit,Dhori Area							
	Category of Services (To Be Selected by Department)		Category of Bidder( To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :			Select	18.00	0.00	0.00	
<p align="center"><b>PRICE SCHEDULE</b></p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )</p>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	
1	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc:External work:80 mm dia nominal bore	1000	metre	768.15	768150.00	INR Seven Lakh Sixty Eight Thousand One Hundred & Fifty Only	
2	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. (external work):50 mm dia. nominal bore	1600	metre	543.4	869440.00	INR Eight Lakh Sixty Nine Thousand Four Hundred & Forty Only	
3	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. (external work):25 mm dia. nominal bore	60	metre	339.7	20382.00	INR Twenty Thousand Three Hundred & Eighty Two Only	
4	Providing and fixing gun metal gate valve with C.I. wheel of approved quality(screwed end) :80 mm nominal bore.	4	each	1933.85	7735.40	INR Seven Thousand Seven Hundred & Thirty Five and Paise Forty Only	
5	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end):50 mm nominal bore	6	each	762.45	4574.70	INR Four Thousand Five Hundred & Seventy Four and Paise Seventy Only	
6	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end): 25 mm nominal bore	10	each	462.15	4621.50	INR Four Thousand Six Hundred & Twenty One and Paise Fifty Only	

7	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	10000	ltrs	8.4	84000.00	INR Eighty Four Thousand Only
8	Providing and fixing PTMT bib cock of approved quality and colour.15mm nominal bore, 86 mm long, weighing not less than 88 gms.	40	each	95.35	3814.00	INR Three Thousand Eight Hundred & Fourteen Only
9	Earth work in excavation by mechanical means (Hydraulic Excavator )/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	10.13	Cum	188.45	1909.00	INR One Thousand Nine Hundred & Eight and Paise One Hundred Only
10	Supplying and filling in plinth with Jamuna sand under floors including, watering, ramming consolidating and dressing complete.	1.13	Cum	1844	2083.72	INR Two Thousand & Eighty Three and Paise Seventy Two Only
11	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	8.5	Cum	6490.9	55172.65	INR Fifty Five Thousand One Hundred & Seventy Two and Paise Sixty Five Only
12	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	22.5	Cum	5322.15	119748.38	INR One Lakh Nineteen Thousand Seven Hundred & Forty Eight and Paise Thirty Seven Only
13	12 mm cement plaster finished with a floating coat of neat cement of mix1:4 (1 cement: 4 fine sand)	72	Sqm	284.75	20502.00	INR Twenty Thousand Five Hundred & Two Only
14	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :50 to 80 mm nominal bore	15	each	1223.65	18354.75	INR Eighteen Thousand Three Hundred & Fifty Four and Paise Seventy Five Only
15	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :25 to 40 mm nominal bore	10	each	590.95	5909.50	INR Five Thousand Nine Hundred & Nine and Paise Fifty Only
16	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer in charge.1:3:6 or richer mix	8	cum	1412.4	11299.20	INR Eleven Thousand Two Hundred & Ninety Nine and Paise Twenty Only
17	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m	12	cum	114.4	1372.80	INR One Thousand Three Hundred & Seventy Two and Paise Eighty Only

18	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions etc. complete (The tail pieces, tapers etc if required will be paid separately) :80mm dia	2	each	5416.4	10832.80	INR Ten Thousand Eight Hundred & Thirty Two and Paise Eighty Only
19	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					2009902.39	INR Twenty Lakh Nine Thousand Nine Hundred & Two and Paise Thirty Nine Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only