

Name of the Work - providing and fixing of garden top lantern lights and lighting accessories in the park(front side of PO office) and beside the parking area of administrative building for beautification of existing park under Rajrappa washery project.

ITC Available

SI .No	Description	Quantity	Units	Rate
1	Providing and fixing of Garden Post Top Lantern light fitting 36/25 W	41.00	Nos.	
2	Cost of PVC insulated and PVC sheathed/XLPE copper cable of 1.1 KV grade 4 Core X 2.5 sq mm	220.00	mtr	
3	Laying of one number PVC insulated and PVC sheathed /XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. Up to 35 Sq mm	190.00	Nos.	
4	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 6 way double door	3.00	Nos.	
5	Supplying and fixing 5A to 32 A rating, 240/415V, 10kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MOB DB complete with connections, testing and commissioning etc. as required.			
5.1	Single pole	9	Nos.	
5.2	Double pole	3	Nos.	
6	Street Light Control Panel, Single Phase, 32 A Timing accuracy	1.00	Nos.	
7	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/coke and salt as required.	2.00	set	
8	Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing along with existing surface/ recessed conduit/ submainwiring/cable as required.	20.00	Nos.	
9	Total impact of gst	1	no	
10	Total	1	no	