

Tender Inviting Authority: Staff officer (E&M), Amrapali- Chandragupta Area, CCL						
Name of the Work / Contract No:	Providing and Fixing Air Break Switch, Drop Out Fuse in HT side and outdoor cable termination work in LT side with other accessories work of two nos. Transformer installed near pit office and Shivpur Railway Siding and provision of Earth Leakage Relay protetction system with CBCT in main control panel in DG sets and its distribution panel at Amrapali OCP, under A-C Area				NIT No: G.M.(A-C)/S.O.(E&M)/e-NIT/25-26/08 ; Dated: 31.05.2025	
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)				
I TC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Providing and fixing of vertical type air break switch 11KV, 3Pole, 400A with all accessories as required	1.000	Sets		0.00	INR Zero Only
2	Providing and fixing of vertical type air break switch 11KV, 3Pole, 200A with all accessories as required	1.000	Sets		0.00	INR Zero Only
3	Providing and fixing of Drop out fuse unit 11 KV, 3 Pole, 400A with all accessories as required	1.00	Sets		0.00	INR Zero Only
4	Providing and fixing of Drop out fuse unit 11 KV, 3 Pole, 200A with all accessories as required	1.00	Sets		0.00	INR Zero Only
5	Supplying and erection of a set of cross bracing FRLSame work for 11 KV over head line double pole structure having four members fabricated out of 50 mm X 50 mm X 6 mm angle iron to form a rectangle of minimum size 1400 mm width X 2500 mm height, complete with 50 mm X 6mm M.S. flat iron clamps, bolts and nuts including drilling holes for insulator pins, bolts and nuts etc (as per drawing) and painting with primer and finish paint as required.	2.00	Sets		0.00	INR Zero Only

6	Supplying, installing, testing and commissioning of 400A TPN capacity End Feed Unit made of 1.6mm thick sheet steel enclosure duly painted with powder coating to existing rising mains complete with TPN disconnecter FSU and HRC fuses, mounting stands, cable end box, brass compression gland, connections, earthing etc. as required.	1.00	Each		0.00	INR Zero Only
7	Supplying and making outdoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for following size of 3 core, XLPE aluminium conductor cable of 11 KV grade as required : 240 sq. mm	4.00	Each		0.00	INR Zero Only
8	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	2.00	Sets		0.00	INR Zero Only
9	Providing and laying earth connection from earth electrode with 6 SWG dia G.I. Wire in 15 mm dia G.I. pipe from earth electrode including connection with G.I. thimble excavation and re-filling as required.	110.00	Mtr.		0.00	INR Zero Only
10	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 3½ X 240 sq. mm (62mm)	22.00	Each		0.00	INR Zero Only
11	Providing and fixing 400 A,50KA,FPMCCB rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required.	5.00	Each		0.00	INR Zero Only
12	Providing, fixing and testing of Earth Leakage relay with all accessories on exisiting MCCB pannel as per inclosed analysis-1	11.00	Each		0.00	INR Zero Only
13	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only	