

Tender Inviting Authority: Staff Officer Civil Piparwar Area.

Name of Work : Repair of damaged boundary wall of Anand Vihar Colony under Gm Unit, Piparwar Area.

.	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder( To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>		
<b>ITC Not Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18.00</b>	<b>0.00</b>	<b>0.00</b>

**PRICE SCHEDULE**

**(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )**

<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER</b>	<b>NUMBER #</b>	<b>TEXT #</b>
<b>Sl. No.</b>	<b>Item Description</b>	<b>Quantity</b>	<b>t</b>	<b>Estimated Rate in Rs. P</b>	<b>TOTAL AMOUNT in Rs. P</b>	<b>TOTAL AMOUNT In Words</b>
<b>1</b>	<b>2</b>	<b>3</b>	<b>4</b>	<b>5</b>	<b>6</b>	<b>7</b>
1.01	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	50.540	Cum	188.45	<b>9524.26</b>	INR Nine Thousand Five Hundred & Twenty Four and Paise Twenty Six Only
1.02	Supplying and filling in plinth with Jamuna sand under floors, including watering, ramming, consolidating and dressing complete.	0.290	Cum	1844.00	<b>534.76</b>	INR Five Hundred & Thirty Four and Paise Seventy Six Only
1.03	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	4.220	Cum	5167.75	<b>21807.91</b>	INR Twenty One Thousand Eight Hundred & Seven and Paise Ninety Only
1.04	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	18.950	Cum	7365.50	<b>139576.23</b>	INR One Lakh Thirty Nine Thousand Five Hundred & Seventy Six and Paise Twenty Three Only
1.05	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	12.640	Cum	8441.35	<b>106698.66</b>	INR One Lakh Six Thousand Six Hundred & Ninety Eight and Paise Sixty Six Only

1.06	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	31.590	sqm	262.55	<b>8293.95</b>	INR Eight Thousand Two Hundred & Ninety Three and Paise Ninety Five Only
1.07	Centering and shuttering including strutting, propping etc. and removal of form for : Walls (any thickness) including attached pilasters, buttersesses, plinth and string courses etc.	126.360	sqm	538.75	<b>68076.45</b>	INR Sixty Eight Thousand & Seventy Six and Paise Forty Five Only
1.08	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.Thermo-Mechanically Treated bars	3159.000	Kg	75.85	<b>239610.15</b>	INR Two Lakh Thirty Nine Thousand Six Hundred & Ten and Paise Fifteen Only
1.09	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	<b>0.00</b>	<b>0.00</b>	INR Zero Only
<b>Total in Figures</b>					<b>594122.37</b>	INR Five Lakh Ninety Four Thousand One Hundred & Twenty Two and Paise Thirty Seven Only
<b>Quoted Rate in Figures</b>			Select		<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>		<b>INR Zero Only</b>				