Validate	Print Help		item	Rate BoQ			
Tender Inviting Auth	nority: Staff Officer(E&T), BnK Area.						
Name of the Work / Contract No:	Re-wiring and restoration of Telephone Line installed in GM Unit (G.M Office, Guest House, Officers Club and GM Bungalow) along with dismantling of old telephone cables and exchange at B&K Area						
	Category of Services (To Be Selected by Department)		Category of Bidder (To Be	To Be Entered by Department			
ITC Available	Works Contract		Bidder's Status (Mandatory	Rate of GST	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00	0.0
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT#	NUMBER	NUMBER #	NUMBER #	TEXT #
SI. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Supplying and drawing 1 pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required.		mtrs				INR Zero Only
2	Supplying and fixing of 20 mm of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.		mtrs			0.00	INR Zero Only
3	Supplying and fixing of 32 mm of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.		mtrs			0.00	INR Zero Only
4	Supplying and fixing telephone socket outlet modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.		each			0.00	INR Zero Only
5	Supplying and fixing 1 or 2 module (75mm * 75mm), GI box alongwith modular base & cover plate for modular switches in recess etc. as required.	25	each			0.00	INR Zero Only
6	Supplying and fixing of 50 pair Telephone Distribution Box/ Junction box with krone module	3	each			0.00	INR Zero Only
7	Supplying and drawing of 1 run of UTP 4 pair CAT 6 LAN cable in the existing surface/recessed steel/PVC conduit as required	300	mtrs			0.00	INR Zero Only
8	Dismantling of existing 20 pair and 50 pair telephone cable		mtrs			0.00	INR Zero Only
9	Laying of 10 pair and 20 pair telephone cable		mtrs				INR Zero Only
10	Fabrication of 240 Volts DC battery stand along with fitting and fixing of battery and stand	1	Each				INR Zero Only
11	Dismantling of exisiting network rack, UPS of VTS control room along with all network equipment and safe storage of equipment to GM Office E&T store	1	each			0.00	INR Zero Only
12	Dismantling of old card based telephone exchange and safe storage to store		each				INR Zero Only
19	Total impact of GST for the purpose of CTC	1.000	No.		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Wor	Words INR Zero Only						