

Validate	Print	Setup	Item Rate Bid			
Tender Invoking Authority: Staff officer (E&M), Magadh - Sanghumdra Area, CCL						
Name of the Work/ Contract No.	Work of "Repairing the false ceiling and wiring, with some modification of the two-number portable cable to make it suitable for fixing various bus bars and relay panels to safely control the power supply under Magadh DCT, M-S area."			NT No: G.M/(M-S)/S.O.(E&M)is-NT/25-26/29, Dated:- 21.06.2025.		
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by)				
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(In Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By C/L Subsidary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00	
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be updated after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only.)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	Part (A) For Shelter modification Work:-	3	4	6	7	8
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work. Including cutting, bolting, fixing in position and applying a priming coat of approved steel primer all complete.	495.6	Kg		0.00	INR Zero Only
2	Providing corrugated G.S. sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.Limpet washers or with G.L. Limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/vertical or curved surfaces), excluding the cost of purline, rafters and trusses and including cutting to size and shape wherever required. 0.80 mm thick with zinc coating not less than 275 gm/sq meter X 5mm x 30mm	60	sqm		0.00	INR Zero Only
3	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS-733 and IS-1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, a. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mixed and jointed mechanically wherever required, including cleat angle. Aluminium snap heading for glazing I paneling, C.P. brass/stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) Anodised aluminium (anodized transparent or dyed to required shade according to IS-1868, Minimum anodic coating of grade AC 15)	60	sqm		0.00	INR Zero Only
4	Providing and fixing M.S. grills of required pattern in frames of windows etc. with MS flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding	36	kg		0.00	INR Zero Only
5	Providing and saying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement-All work up to plinth level 12.5 CM (element 3 course and 3 graded stone aggregate 20 nominal size)	72	kg		0.00	INR Zero Only
6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	2.3	cum		0.00	INR Zero Only
7	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/neo prene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap heading shall be paid in basic item) (With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	179.4	sqm		0.00	INR Zero Only
8	Providing and fixing powder coated aluminium work (minimum thickness of powder coating 50 micron) consisting of leaf/angle sections, of approved make conforming to IS-733 in frames of false ceiling including aluminium angle cleats with necessary C.P. brass/stainless steel sunk screws, aluminium perimeter angles fixed to wall with stainless steel rawl plugs 10x50 mm centre to centre and fixing the frame work to G.L. level adjusting hangers 6 mm dia. with necessary cadmium plated machine screws all complete as per approved architectural drawings and direction of the Engineer-in-charge (level adjusting hangers, ceiling cleats and expansion hold fasteners to be paid for separately).	6	sqm		0.00	INR Zero Only
9	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. Solid wood cum Kilm seasoned and chemically treated hollock wood	22.3	sqm		0.00	INR Zero Only
10	Providing and fixing paneling or paneling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows/Area of opening for panel inserts excluding portion inside grooves or rebates to be measured. Paneling for panelled or panelled and glazed shutters 25 mm to 40 mm thick: Plain particle board flat pressed, 3 layer or graded wood particle board medium density Grade 1, IS-3087 marked	0.42	cum		0.00	INR Zero Only
11	Applying priming coat/With ready mixed aluminium primer of approved brand and manufacture on sections wood and ply wood	62.7	sqm		0.00	INR Zero Only
12	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	62.7	sqm		0.00	INR Zero Only
13	Part(B) For shelter electrification:- Wiring for light point (as per instruction (as per point) all bell point with 1.5 sq.m FRLS PVC insulated copper conductor single core cable in surface /recessed medium class PVC conduit, with plane type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.m FRLS PVC insulated copper conductor single core cable etc. as required. Group A for extension of point wiring	62.7	sqm		0.00	INR Zero Only
14	Supplying and fixing metal box of 150mm X 75mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5A socket outlet and 5A A plane type switch, connections, painting etc. as required	24	point		0.00	INR Zero Only
15	Supplying and fixing metal box of 100mm X 100mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 6 pin 5A 15A socket outlet and 15A A plane type	2	Nos.		0.00	INR Zero Only
16	Supplying and fixing brass button/angle holder Including connection etc. as required	24	Nos.		0.00	INR Zero Only
17	Wiring for circuit/submain wiring alongwith earth wire with the 2 X 11.5 sq. mm + 1 X 1.5 sq. mm earth wire size of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.	16	Nos.		0.00	INR Zero Only
18	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required. 2 X 6 sq. mm + 1 X 6 sq. mm earth wire	30	mtre		0.00	INR Zero Only
19	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker single pole and neutral for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required	20	mtre		0.00	INR Zero Only
20	Supplying & fixing suitable size GI box with modular plate and cover in front on surface or in recess including providing and fixing 25 A modular socket outlet and 25 A modular 50 MCB, "C" curve including connections, painting etc. as required.	8	pcs		0.00	INR Zero Only
21	Providing and fixing following rating and breaking capacity MCB with thermomagnetic release and terminal spacers in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required. 100 A, 16 kA, 1TNM CBR	2	pcs		0.00	INR Zero Only
22	Supplying and fixing of following ways surface/recess mounting, vertical type, 415V, 175N MCB distribution board of sheet steel, steel protected, duty link, earth bar, din bar for mounting MCBs (but without MCBs and accessories required). (Note-Vertical type MCB/DB is normally used where 3 phase outlets are required.) way (4+12), Double door Each	2	Nos.		0.00	INR Zero Only
23	Providing of 16 sq mm 4 core/is marked, upto 1.1 kv grade Aluminium armoured cable for laying service wire	2	Each		0.00	INR Zero Only
24	Laying of one number PVC Insulated and PVC sheathed/DLP power cable of size not exceeding 35 sqmm direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. As required	60	mtre		0.00	INR Zero Only
25	Providing of 1 ed tube light 20 watt	50	mtre		0.00	INR Zero Only
26	Providing of 1 ED Bulb 15 watt	8	Nos.		0.00	INR Zero Only
27	Supply of wall mounted fan 400 mm	8	Nos.		0.00	INR Zero Only
28	Providing of exhaust fan of 300 mm diameter	6	Nos.		0.00	INR Zero Only
29	Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.	2	Nos.		0.00	INR Zero Only
30	Earthling with copper earth plate 600 mm X 600 mm X 3mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 27 mm long etc. with channel/slope and salt as required.	2	Nos.		0.00	INR Zero Only
31	Fixing Charge of supplied items up to 26 to 28 at 15% of item cost	2	Nos.		0.00	INR Zero Only
32	Total impact of GST for the purpose of CTC	2	Job		0.00	INR Zero Only
Totals Figures, Quoted Rate in Words		1.00	Job	0.00	0.00	INR Zero Only
				INR Zero Only	0.00	INR Zero Only