

BIIL OF QUANTITY

NAME OF THE WORK		Repairing and maintenance of 03 nos 3.3KV VCB installed at different colonies under kargali OCP, BnK Area			
Sl. No.	Description	Qty	Unit	Rate/Unit in Rs.	Amount in Rs.
1	Supply & providing of selector switch volt & Ampere	4	nos		
2	Supply & Providing of moving contact	2	nos		
3	Supply & providing of Misc nut bolt & washer	1	LS		
4	Supply & providing of shunt trip coil with 110V	3	nos		
5	After repairing of breakers its complete testing by secondary injection set machine through all protective relay , CT, PT etc.	3	nos		
6	Rectification of control tripping circuit wiring including some materials lugs, clips, sockets etc.	3	set		
7	Repairing setting of operative mechanism	2	set		
8	supply & providing of fixed contact	2	nos		
9	Supply & providing of Auxiliary switch	2	nos		
10	Supply & providing of bus bar flower contact	2	nos		
11	Supply & providing of PT 3.3KV/110V dry type	1	no		
12	Supply & providing of closing coil	2	nos		
13	Supply & providing of earth leakage relay	1	no		
14	Supply & providing of PT fuse	6	nos		
15	Supply & providing of bushing insulator	2	nos		
16	Supply and Providing of HRC fuse	9	nos		
17	Supply and providing of rectifier unit 110V	2	nos		
18	supply & providing of CBCT	2	nos		
19	Supply & providing of Electronic type microprocessor based O/C &E/F relay(JVS)	1	no		
20	Supply and providing of push switch	4	nos		
21	Supply & providing of indicator	4	nos		
22	complete switch repairing /over hauling opening fitting , checking etc with labour cost	3	no		
23	Supervision ,incidental charges , tools and tackles & over head expanse etc.	1	no		
	GST@18%				
	Total inclusive of GST				

PE(E&M)/Kargali OCP