

Tender Inviting Authority: SOE&M,GM Unit Kuju

Name of the Work / Contract No:

Maintenance and installation of lighting Arrestor Station Type 11KV and 3.3KV at site Banwar subststion of Topa Project under Kuju Area.

NIT No. : GM (K)/EnM/e-Tender/25-26/78

	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
2	Supply & Fixing of Lighting Arrestor line type/ Station Type 9 KV, 12 KA	9.00	no			0.00	INR Zero Only
3	Supply & Fixing of Lighting Arrestor Station Type 3.3 KV	6.00	no			0.00	INR Zero Only
4	Supply & Fixing of Support Insulator, 11KV grade dia 75mm length 90mm	45.00	no			0.00	INR Zero Only
5	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required 25 mm	105.00	mtr			0.00	INR Zero Only
6	Supply & Fixing of PG Clamp	9.00	no			0.00	INR Zero Only
7	Supply & Fixing of copper cable single core flexible type 1100 voltage grade 16 sq mm	160.00	mtr			0.00	INR Zero Only
8	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required	5.00	no			0.00	INR Zero Only
9	Supply & Fixing of Aluminium Tubular Lug 35 sq mm	10.00	no			0.00	INR Zero Only
10	Supplying of two lengths of channel iron 75 mm X 40 mm X 6 mm(7.14 kg per metre) double pole cross arm for three wire 11KV over head line conductors complete with through bolts and nuts for clamping to the poles, 50 mm X 6 mm M.S. flats welded on one side to the channel iron and with bolts and nuts on the otherside for tying the cross arms together, including drilling holes for insulator pins/ fittings, bolts, nuts and washers	5.00	no			0.00	INR Zero Only
11	Supply & Fixing of Nut & Bolts (5/8" X 3")	24.00	kg			0.00	INR Zero Only
12	Supply & Fixing of Pad/Palm connector Minimum thickness 2 millimeter, 800Amp, 400 kiloVolt	24.00	no			0.00	INR Zero Only
13	Total impact of GST for the purpose of CTC	1.000	nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						