

Item Rate BoQ

Tender Inviting Authority:	Asst. Manager (CP)/Kedla Washery.
Name of the Work / Contract No:	Different offloading & repairing works for revival of 244B screen of main plant at Kedla Washery. NIT No-PO/KWE-Tender/25-26/ 04 date:-19.06.2025

	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes In Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	A. Off-loading & repairing works for revival of 244B screen for recovery of fines in slurry circuit Re-handling of slurry from the bed & under flow pipe and hopper of 244B screen	26.776	M ³			0.00	INR Zero Only
2	Dismantling of bearing assembly from 244B and fitted in 244A screen. (a) Dismantling of brg. Housing assly. from 244Bscreen.	1.560	MT			0.00	INR Zero Only
3	(b) Shifting of assemblies to work shop for repairing and repaired assemblies for fitting in 244B.	3.120	MT			0.00	INR Zero Only
4	(c) Installation of assemblies in 244B.	1.560	MT			0.00	INR Zero Only
5	Dismantling of screen panels & motor of screen and re-fitting of panels. (a) Dismantling of screen panels & motor	3.806	MT			0.00	INR Zero Only
6	(b) Shifting of dismantled panels & motors to store in room and Shifting of screen panels & motors for installation.	7.612	MT			0.00	INR Zero Only
7	(c) Re-installation of screen panels & motors	3.806	MT			0.00	INR Zero Only
8	Fabrication and fitting of side plates.	0.158	MT			0.00	INR Zero Only
9	Dismantling & hanging of screen for rubber buffer support rectification and re-installation of the same. (a) Dismantling & hanging of screen for rubber buffer support rectification.	9.077	MT			0.00	INR Zero Only
10	(b) Re-installation and alignment of the screen.	9.077	MT			0.00	INR Zero Only
11	(B) Repairing & rotating of under flow of 244B screen. (a) Dismantling of under flow pipe.	0.858	MT			0.00	INR Zero Only
12	(b) Re-installation and alignment of pipe	0.858	MT			0.00	INR Zero Only
13	(C) Re-installation and alignment of snapped under hopper of 244B screen (a) Dismantling of 244B screen under hopper.	4.877	MT			0.00	INR Zero Only
14	(b) Installation & alignment of under hopper of 244B screen after fabrication & erectron stengthening of hoppers supports.	4.877	MT			0.00	INR Zero Only
15	(c) Dismantling & hanging of screen for rubber buffer replacement.	9.077	MT			0.00	INR Zero Only
16	(d) Re-Installation and alignment of the screen 244B.	9.077	MT			0.00	INR Zero Only
17	Total Impact of GST for the purpose of CTC	1.00	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words							INR Zero Only