

Tender Inviting Authority: SOE&M\GM Unit Kulu						
Name of the Work / Contract No:	Providing power supply with proper lighting conductor and earthing arrangements at 2 nos.RFID Checkpost at Topa OCP Under Kulu Area.			NIT No. : GM (K)/EnM/e-Tender/25-26/87		
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST (in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIU/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00
<b>PRICE SCHEDULE</b> (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P
1	2	3	4	5	6	7
2	Erection of pole of following length in cement concrete 1:3:6 (1 cement 3 coarse sand: 6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc. as required. Above 10.00 metre and upto 12.00 metre	4.00	nos			0.00 INR Zero Only
3	Supplying and erection of galvanised 'D' iron clamps complete with shackle insulator (100mm X 110mm), G.I. bolts, nuts and washers, coach screws etc. as required	8.00	nos			0.00 INR Zero Only
4	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required	224.00	kg			0.00 INR Zero Only
5	Supplying of two lengths of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) double pole cross arm for three wire 11K Vover head line conductors complete with through bolts and nuts for clamping to the poles. 50 mm X 6 mm M.S. flats welded on one side to the channel iron land with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/ fittings, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required	1.00	nos			0.00 INR Zero Only
6	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required	3.00	nos			0.00 INR Zero Only
7	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. Spindle and nuts etc, as required	16.00	nos			0.00 INR Zero Only
8	Supplying and erection of bow stay set complete (galvanised with: 1920mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45cmx 17.5 mm, thimble, stay clamps, turn buckle (20 mm X 60 cm), 714.00 mm dia G.1. stay wire and strain insulator etc in cement concrete 1:3:5 (1 cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and also with 0.6 m long brace of size 50 mm X 50 mm X 6 mm angle iron with 50 mm de pulley fixed at one end of the brace as required.	2.00	set			0.00 INR Zero Only
9	Supply & Fixing of LT PVC Spacers	40.00	nos			0.00 INR Zero Only
10	Dismantling of over head lines comprising of copper/ aluminium over head conductor, G.I. wire, cross arms, insulators etc, as required	260.00	kg			0.00 INR Zero Only
11	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required.	4.00	nos			0.00 INR Zero Only
12	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required	8.00	nos			0.00 INR Zero Only
13	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in Cement mortar 1:4 (1 cement. 4 coarse sand) For old Earth pits 0.12 MX75X0.50M X 4 Side X 8 Nos ~1.44 CUM	1.44	cum			0.00 INR Zero Only
14	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement: 1.5 coarse sand (zone-II); 3 graded stone aggregate 20 mm nominal size) 075 Mtr X 10.75 Mtr X 0.12 Mtr X. 8 Nos=0.54 CUM	0.54	cum			0.00 INR Zero Only
15	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more	43.20	kg			0.00 INR Zero Only
16	Painting of poles of 11 mtr (8 Nos X 9.04 SQM-72.32 SQM)	72.32	sqm			0.00 INR Zero Only
17	Supply & Fixing of D' iron clamp	48.00	nos			0.00 INR Zero Only
18	Supply & Fixing of Stay wire (7/4.00 mm dia.)	395.00	kg			0.00 INR Zero Only
19	Supply & Fixing of Aluminium Unarmoured single core flexible type 1100 voltage grade 35 sq mm	280.00	mtr			0.00 INR Zero Only
20	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required 25 mm	200.00	mtr			0.00 INR Zero Only
21	Supply & Fixing of Aluminium Tubular Lug 35 sq mm	16.00	nos			0.00 INR Zero Only
22	Supply & Fixing of copper material, Tripod lightning conductor, 30 inch length X 25mm top X 50mm bottom, 12.5mm thick rod	8.00	nos			0.00 INR Zero Only
23	Supply & Fixing of Post Insulator, 10KA, 11KV rated, standard size	8.00	nos			0.00 INR Zero Only
24	Total Impact of GST for the purpose of CTC	1.000	nos		0.00	0.00 INR Zero Only
Total in Figures						0.00 INR Zero Only
Quoted Rate in Words						INR Zero Only