

Tender Inviting Authority: SOE&M),GM Unit Kuju							
Name of the Work / Contract No:				upgradation and re-wiring of all offices and barandah of Ara Project Office Building, fresh wiring of Kali Mandir near PO Office building and fresh wiring of Dumerbera Sub-station SBA rooms of Ara colliery under Kuju Area.			
				NIT No. : GM (KJ)EnM/e-Tender/25-26/84			
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)		To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(In Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7	8
2	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq mm FRLS PVC Insulated copper conductor single core cable in surface /recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sqmm FRLS PVC insulated copper conductor single core cable etc. as required. Group A	17.00	nos			0.00	INR Zero Only
3	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC Insulated copper conductor single core cable in surface /recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group B	31.00	nos			0.00	INR Zero Only
4	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed steel conduit as required. 2x2.5sq.mm + 1x2.5sq.mm earth	355.00	M			0.00	INR Zero Only
5	Supplying and drawing following sizes of FRLS PVC Insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required. 4 x 6 sq.mm. For service connection	60.00	M			0.00	INR Zero Only
6	Supplying and fixing 16 way double door, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with lined copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator)	1.00	nos			0.00	INR Zero Only
7	Supplying and fixing 8 way double door, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/recess, complete with lined copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator)	1.00	nos			0.00	INR Zero Only
8	Supplying and fixing of 5A to 32A rating, 240/415 V, 10KA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. single pole	20.00	nos			0.00	INR Zero Only
9	Supplying and fixing of 5A to 32A rating, 240/415 V, 10KA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. single pole and neutral	1.00	nos			0.00	INR Zero Only
10	Supplying and fixing following rating, double pole, (single phase and neutral), 240 V, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required. 25 A	3.00	nos			0.00	INR Zero Only
11	Supplying and fixing metal box of 150mm X 750mm X 60mm deep (nominal size) on surface or in recess with splat size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5/6 A socket outlet and 5/6 A piano type switch, connections, painting etc. as required.	21.00	nos			0.00	INR Zero Only
12	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	22.00	nos			0.00	INR Zero Only
13	Providing and fixing following capacity TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required. 63A	1.00	nos			0.00	INR Zero Only
14	Providing and fixing following capacity TP&N bisconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required. 32A	1.00	nos			0.00	INR Zero Only
15	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	14.00	nos			0.00	INR Zero Only
16	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required. For Earth Wire erection at PO office and Dumerbera Sub-station	2.00	nos			0.00	INR Zero Only
17	Supply and installation of wired Call Bell, 220V rated	5.00	nos			0.00	INR Zero Only
18	Supply and installation of 220V rated, Electric industrial Siren having range of 1KM for theft and fire alert at	2.00	nos			0.00	INR Zero Only
19	Supply and installation of, 15 Watt, Bulkhead LED light, white	17.00	nos			0.00	INR Zero Only
20	Supply and installation of white LED, 15 Watt, Surface ceiling light	26.00	nos			0.00	INR Zero Only
21	Total Impact of GST for the purpose of CTC	1.000	nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words				INR Zero Only			