

Tender Inviting Authority: SOE&M,GM Unit Kuju

Name of the Work / Contract No:	(A) Repairing/Reconditioning of 01 No of 3.3 KV, 160 Amp, 360 KW rated, Sait teknik Pvt. Ltd. Make DOL satrter, SL. No.-SAHD-2723 installed at Quarry no.-1 of Pundi Project for starting 2000 GPM Pump-Motor set and (B) Repairing/Reconditioning of 01 nos. of L&T Put make, ACB LT Panel sl.no. LW00355, installed at Pundi colony sub-station of Pundi Project under Kuju Area.			NIT No. : GM (K)/EnM/e-Tender/25-26/62		
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
2	(A) Repairing/Reconditioning of 01 No of 3.3 KV, 160 Amp, 360 KW rated, Sait teknik Pvt. Ltd. Make DOL, satrter, SL. No.-SAHD-2723 installed at Quarry no. 1 of Pundi Project for starting 2000 GPM Pump-Motor set.						
3	Supply and fixing of AMP Meter, 0-200 A range, 110V, 4" Sq mm. size	1.00	Nos			0.00	INR Zero Only
4	Supply and installation of Analog Volt Meter, 0-15KV range, 110V, 4" Sq mm. size	1.00	Nos			0.00	INR Zero Only
5	Supply and installation of Selector Switch, 16A rated	2.00	Nos			0.00	INR Zero Only
6	Supply and installation of IDMT type earth leakage relay, 110V AC/DC rated and with current setting range of 0.5-8 A, along with CBCT	1.00	Nos			0.00	INR Zero Only
7	Repairing of isolator of starter	1.00	job			0.00	INR Zero Only
8	Supply and installation of motor protection relay, 110V operated and suitable for 3.3KV, 360KW rated DOL starter, having feature for protection against Over load, single phasing, locked rotor, carth fault and under current	1.00	Nos			0.00	INR Zero Only
9	Supply and fixing of moulded ring type CT, having 100/5 A current rating along with test certificate	3.00	nos			0.00	INR Zero Only
10	Wiring with ferrule, lug, PVC copper cable e.t.c. required	1.00	Nos			0.00	INR Zero Only
11	B):-Repairing/Reconditioning of 01 nos of L&T Pvt make, ACB LT Panel sl.no.- 1 W00355, installed at Pundi colony sub-station.						
12	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, cic as required 630 A, SOKA. TPMCCB	2.00	Nos			0.00	INR Zero Only
13	Supply and installation of Aluminum Alloy bus-bar strip of dimension 50 mm x 5mm	15.00	kg			0.00	INR Zero Only
14	Supply and installation of LT analog ampear meter, 0-500 A range	3.00	Nos			0.00	INR Zero Only
15	Supply and installation of LT analog Volt meter. 0-500 V range	3.00	Nos			0.00	INR Zero Only
16	Supply and installation of ring type LT Current Transformer 500A/5A	9.00	Nos			0.00	INR Zero Only
17	Supply an installation of selector switch rotary type 6 A rated	6.00	Nos			0.00	INR Zero Only
18	Supply an installation of Indicating lamp. 220V rated	6.00	Nos			0.00	INR Zero Only
19	Wiring with ferrule, lug, PVC copper cable e.t.c. required	1.00	Nos			0.00	INR Zero Only
20	Total Impact of GST for the purpose of CTC	1.000	nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						