Validate	Print	Help

Quoted Rate in Words

Validate Print	Print Help Item Rate BoQ							
Tender Inviting Authority: Staff	officer(E&M), Piparwar Area							
Name of the Work / Contract No:	Contract Replacement and maintenance of GOAB Switch and Horngap fuse unit set at different Substation under Township (Bachra), GM Unit, Piparwar Area.				NIT No. : SO(E&M)/PPR/e-NIT/25-26/12			
	Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Not Available	Works Contract		Bidder's Status (Mandatory)		Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00	0.0	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)								
NUMBER #	TEXT#	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #	
Si. No.	Item Description	Quantity	Units	Estimated Rate (Without Taxes) in Rs. P		TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words	
1	2	3	4	5	6	7	8	
1	Erection of steel tubular or rail pole strut in cement concrete 1:36 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and secured with holding clamps, bolts, nuts, etc. as required.	2	no	6508.00		0.00	INR Zero Only	
2	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required.	2	no	1875.00		0.00	INR Zero Only	
3	Erection of all aluminium conductor of 7/3.40mm to 7/4.00mm diameter and above including binding etc. as required. Erection (1 span, 30mtr, 3wire system, 0.394kg/m)	35.5	kg	147.00		0.00	INR Zero Only	
4	Supplying of two lengths of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) double pole cross arm for three wire 11KV ower head line conductors complete with through botts and nuts for clamping to the poles, 50 mm X 6 mm M.S. flast wedded on eside to the channel iron and with botts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/ fittings, botts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required.	2	set	4158.00		0.00	INR Zero Only	
5	Supplying and erection of 11 KV pin insulator complete with large steel head G.I. pin, nuts, washers etc. as required.	6	set	249.00		0.00	INR Zero Only	
6	Supply & fixing of PG clamp required for connection	36	nos	1232.31		0.00	INR Zero Only	
7	Erection of GOAB Switch 11KV Rating	8	no	4119.30		0.00	INR Zero Only	
8	Providing & fixing of Horngap Fuse Set 11KV rating	6	no	9053.95		0.00	INR Zero Only	
9	Supplying and making outdoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for 120Sqmm size of 3 core, XLPE aluminium conductor cable of 11 KV grade as required:	20	nos	17427.00		0.00	INR Zero Only	
10	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 11 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. Upto 120 sq. mm	180	mtr	370.00		0.00	INR Zero Only	
11	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only	
Total in Figures						0.00	IND 7 Oak	

INR Zero Only