

Tender Inviting Authority: Staff officer(E&M), Piparwar Area

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (Without Taxes) in Rs. P	BASIC RATE (Without Taxes) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Dismantling of O/H lines comprising of copper/aluminium O/H conductor,G.I.wire,cross arms, insulators etc.(19 span, 40mtr, 5wire system, 0.214kg/m =813.20 kg + 5 span, 40mtr, 3 wire system, 0.394 kg/m = 236.40 kg) =813.20 kg + 236.40 kg = 1049.60 Kg	1049.6	kg	64.00		0.00	INR Zero Only
2	Dismantling of pole/street light standard/strut embedded in brick ballast foundation etc.as required.	16	Nos	1412.00		0.00	INR Zero Only
3	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and secured with holding clamps, bolts, nuts, etc. as required.	16	nos	6508.00		0.00	INR Zero Only
4	Erection of all aluminium conductor of 7/3.40mm to 7/4.00mm diameter and above including binding etc. as required. (19 span, 40mtr, 5wire system, 0.214kg/m =813.20 kg + 5 span, 40mtr, 3 wire system, 0.394 kg/m = 236.40 kg) =813.20 kg + 236.40 kg = 1049.60 Kg	1049.6	kg	147.00		0.00	INR Zero Only
5	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required .	5	set	1042.00		0.00	INR Zero Only
6	Erection of angle iron/channel iron cross arm on wood/Rcc/ Pcc/ steel tubular/rail pole etc. as required.	5	set	225.00		0.00	INR Zero Only
7	Supplying and erection of stay set complete (galvanised) with 19/20mm dia X 1.8meters long stay rod,anchor plate of size 45cm X 45cm X 7.5mm,thimble,stayclamps,bow lightener,7/3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1cement:3 coarse:6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	8	each	4230.00		0.00	INR Zero Only
8	Supply of Credling 6/8 SWG G.I. wire for credling [10x((0.164x30mtrx2)+(0.164x35) =155.80 kg	155.8	kg	63.00		0.00	INR Zero Only
9	Erection of G.I.wire no.8 SWG including binding etc.	155.8	kg	29.00		0.00	INR Zero Only
10	Supplying and erection of 11/3.3KV pin insulator complete with large steel head G.I. pin, nuts, washers etc. as required.	12	set	249.00		0.00	INR Zero Only
11	Supplying and erection of 11/3.3 KV disc insulator for 11/3.3 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	15	set	818.00		0.00	INR Zero Only
12	Supplying and erection of 75 mm X 90 mm shackle insulator with G. I. Bolt, nuts and straps etc. as required .	36	set	145.00		0.00	INR Zero Only
13	Supplying and erection of 100 mm X 80 mm pin insulator complete with G. I. Spindle and nuts etc. as required .	30	set	119.00		0.00	INR Zero Only
14	Fixing of LED Street Light fitting	10	Nos.	320.16		0.00	INR Zero Only
15	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					