

Tender Inviting Authority: Staff officer(E&M), Piparwar Area

Name of the Work / Contract No:	Wiring and fixing of Garden light at Regional Hospital of Bachra Township under GM Unit, Piparwar Area.	NIT No. : SO(E&M)/PPR/e-NIT/25-26/14				
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)		Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (Without Taxes) in Rs. P	BASIC RATE (Without Taxes) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Suply & fixing of IP65 Inverted Pyramid Tripod type10W LED Bollard with soft 360 deg. Light.	30	nos	7026.36		0.00	INR Zero Only
2	Supply & fixing of 2+2 way, SPN single door MCB DB	30	nos	989.68		0.00	INR Zero Only
3	Supplying and drawing 3 x 4 sq. mm sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.	85	mtr	177.00		0.00	INR Zero Only
4	Supply & fixing of 2.5 sqmm FRLS PVC single core copper cable	90	mtr	36.87		0.00	INR Zero Only
5	Supply & fixing of 50mm dia G.I. pipe (light class)	30	nos	574.30		0.00	INR Zero Only
6	Supplying and laying of 63 mm dia (OD-63 mm & ID-51 mm nominal) size DWV HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14830, Part II complete with fitting and cutting, jointing etc.direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required.	70	mtr	229.00		0.00	INR Zero Only
7	Providing and laying in position cement concrete of 1:3:6 (1 cement : 3 coarse sand : 6 graded stone). Muffling of pipe = 0.44x0.44x0.44x30 no pipe = 2.55 cum	2.55	cum	5916.00		0.00	INR Zero Only
8	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						