

ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(In Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m inwidth as well as 10 sqm on plan) including disposal of excavatedearth, lead upto 50 m and lift upto 1.5 m, disposed earth to be levelled and neatly dressed Ordinary 2.5 M X 1.65 M X 0.5 m X 2 Nos.(TRANSFORMER) = 4.125 cum 3.25 M X 3.0 M X 0.5M X 2 Nos (VCB)=9.75 cum	13.88	Cu.M			0.00	INR Zero Only
1.02	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete 2.5 M X 1.65 M X 0.075 m X 2 Nos.(TRANSFORMER) = 0.618 cum 3.25 M X 3.0 M X 0.075M X 2 Nos (VCB)=1.462 cum	2.08	Cu.M			0.00	INR Zero Only
1.03	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand (zone-III): 6 graded stone aggregate 20 mm nominal size) 2M X 1.15M X 1M X2Nos (TRANSFORMER):- 4.6 cum 2.5M X 2.75M X 1M X 2 Nos(VCB) :- 13.75 cum	18.35	Cu.M			0.00	INR Zero Only
1.04	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete. 2MX0.5MX2 NOS + 1.15MX0.5MX2 NOS (TRANSFORMER) :- 3.15Sqmm 2.5MX0.5MX2NOS + 2.75MX0.5MX2NOS :- 5.25 SQM	8.40	Sq.M			0.00	INR Zero Only
1.05	Laying of one number PVC insulated and PVC sheathed /XLPE power cable of 11KV grade of following size direct in ground including excavation ,sand cushioning, protective covering and refilling the trench etc as required.Above 120sqmm and upto 400sqmm	75.00	Mtrs.			0.00	INR Zero Only
1.06	Providing and fixing 25mmX5mm GI.strip on surface or in recess for connections etc. as required.	65.00	Mtrs.			0.00	INR Zero Only

1.07	500KVA Transformer & VCB shifting with the help of hydraulic jack lifter set M.S rail 90LBS celing D-Link chain pulley and other acessories upto 50mtr	1.00	No.			0.00	INR Zero Only
1.08	250KVA Transformer & VCB shifting with the help of hydraulic jack lifter set M.S rail 90LBS celing D-Link chain pulley and other acessories upto 50mtr	1.00	No.			0.00	INR Zero Only
2	Total impact of GST for the purpose of CTC	1	No.		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					