

ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required. (Above 8.0 mtr and upto 10 mtr)	23.00	Nos.			0.00	INR Zero Only
1.02	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia x 1.8 mtrs. long stay rod, anchor plate of size 45 cm x 45 cm x 7.5 mm, thimble, stay clamps, turn buckle (20mm x 60cm), 7/3.5mm dia G.I stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement: 3course sand: 6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc. as required.	15.00	Nos.			0.00	INR Zero Only
1.03	Erection of angle iron/ channel, iron cross arm on wood/RCC/PCC/Steel tubular/ rail pole etc as required.	60.00	Nos.			0.00	INR Zero Only
1.04	Supplying and erection of 100mm x 110 mm shackle insulator with G.I bolt, nuts and straps etc. as required.	40.00	Sets			0.00	INR Zero Only
1.05	Supplying and erection of 100 mm x 80 mm pin insulator with G.I spindle and nuts etc. as required.	40.00	Sets			0.00	INR Zero Only
1.06	Erection of LV/MV/ shackle/Pin Insulator etc. as required	50.00	Nos.			0.00	INR Zero Only
1.07	Erection of ACSR conductor of 7/2.11 mm to 7/3.00 mm diameter including binding etc as required (20 span x 02 wire x 40 mtr x 0.214 kg/meter = 342.40 kg	342.40	Kgs			0.00	INR Zero Only
1.08	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 mm diameter and above including binding etc. as required (04 span x 04 wire x 40 mtrs. x 0.394 kg/252.16 Kgmeter = 252.16 kg	252.16	Kgs			0.00	INR Zero Only
1.09	Erection of all aluminium conductor of 7/1.96mm to 7/3.10 mm diameter including binding etc. as required (04 span x 5 wire x 40 m x 0.149 kg/m =476.80 kg	476.80	Kgs			0.00	INR Zero Only

1.10	M.S Nut & Bolts 5/8 x 3" and 6" etc as per required sizes	51.00	Kgs			0.00	INR Zero Only
1.11	Dismantling of pole/ street light standard/strut embedded in cement concrete foundation etc. as required	23.00	Nos.			0.00	INR Zero Only
1.12	Dismantling of overhead lines comprising of copper/aluminium over head conductor, G.I wire, cross arms, insulators etc. as required.	500.00	Kgs			0.00	INR Zero Only
1.13	Cradling: Supply & Erection of G.I 8 SWG including binding etc. as required(For cradling 50 m span) 12.25 1. Supply of G.I Wire = 21 kg x Rs.125 = Rs.2625.00 2.Erection of G.I wire= 21 kg x Rs.29 = Rs.609.00 Total = 2625.00+609.00=3234.00	15.00	Sets			0.00	INR Zero Only
1.14	Providing and fixing of lightning conductor finial, made of 25 mm dia 300 mm long, G.I. tube, having single prong at top, with 85 mm dia 6 mm thick G.I. base plate including holes etc. complete as required	10.00	Sets			0.00	INR Zero Only
1.15	Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/coke and salt as required.	10.00	Sets			0.00	INR Zero Only
1.16	Providing and fixing 25 mm x 5 mm G.I. strip on surface or in recess for connections etc. as required	180.00	Mtrs.			0.00	INR Zero Only
1.17	Supply & fixing of LT line separator/spacer PVC, 2 wire, AAA rabbit conductor rate (55 sq. mm)	25.00	Nos.			0.00	INR Zero Only
1.18	Supply & fixing of LT line separator/spacer PVC, 4 wire AAA dog conductor (125 sq. mm)	25.00	Nos.			0.00	INR Zero Only
1.19	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 2 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required	10.00	Sets			0.00	INR Zero Only
1.20	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) cross arm for 4 wire over head line complete with clamps, bolts, nuts and washer etc including drilling of holes for insulator pins etc (as per drawing) and painting with primer and finished paint as required.	10.00	Sets			0.00	INR Zero Only
1.21	Market Supply of G.I 8 SWG including binding etc. as required (Supply of G.I Wire =30Sx40mx1W=1200 m x 0.103 kg/m=123.60 Kgs)	123.00	Kgs			0.00	INR Zero Only
1.22	Erection of G.I Wire	206.00	Kgs			0.00	INR Zero Only
2	<b>Total impact of GST for the purpose of CTC</b>	1	No.		0.00	0.00	INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	INR Zero Only

Quoted Rate in Words	INR Zero Only
----------------------	---------------