

Validate

Print

Help

Item Rate BoQ

| | | | | | | |
|--|---|----------|---|--|-------------------------------------|---|
| Tender Inviting Authority: Project Engineer (E&M),Rohini Project,NK Area, CCL | | | | | | |
| Name of the Work / Contract No: | ERECTION AND DISMANTLING OF POLES AND OH MATERIALS FOR RE-ARRANGEMENT OF 415/220V LIGHTING LINES TO ILLUMINATE NEW DUMP YARD AND HAUL ROAD FROM WORK SHOP CHOWK TO COAL STOCK NO -25 UNDER ROHINI OCP | | | NIT No. PE(EnM)RHN/eNIT/2025-26/03; dated 02.07.2025 | | |
| | Category of Services (To Be Selected by Department) | | Category of Bidder (To Be Selected by Bidder) | | | |
| ITC Available | Works Contract | | Bidder's Status (Mandatory) | Total GST(in Rs.) | GST to be Paid By Bidder (in Rs.) | GST to be Paid By CIL/Subsidiary (in Rs.) |
| Name of the Bidder/ Bidding Firm / Company : | | | Select | 0.00 | 0.00 | 0.00 |
| PRICE SCHEDULE | | | | | | |
| (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only) | | | | | | |
| NUMBER # | TEXT # | NUMBER # | TEXT # | NUMBER # | NUMBER # | TEXT # |
| Sl. No. | Item Description | Quantity | Units | BASIC RATE In Figures To be entered by the Bidder in Rs. P | TOTAL AMOUNT Without Taxes in Rs. P | TOTAL AMOUNT In Words |
| 1 | 2 | 3 | 4 | 6 | 7 | 8 |
| 1 | Erection of metallic pole of following length in cement concrete 1:3:6 (1cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required. Above 10 mtrs upto 12 mtrs | 2.00 | no | | 0.00 | INR Zero Only |

| | | | | | | |
|-------------------------|--|--------|-----|------|------|---------------|
| 2 | Erection of metallic pole of following length in cement concrete 1:3:6 (1cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.above 8 mtrs upto 10 mtr | 7.00 | no | | 0.00 | INR Zero Only |
| 3 | Erection of metallic pole of following length in cement concrete 1:3:6 (1cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation excavation and refilling etc. as required.aboe 6.5 mtr upto 08 mtrs | 13.00 | No | | 0.00 | INR Zero Only |
| 4 | Dismantling of pole/ street light standard / strut embedded in cement concrete foundation etc. as required. | 12.00 | No | | 0.00 | INR Zero Only |
| 5 | Providing and Erection of stay set complete (galvanised) in cement concrete 1:3:6 (1 cement :3 coarse sand : 6graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required. | 6.00 | no | | 0.00 | INR Zero Only |
| 6 | Erection of angle iron/ channel iron cross arm on wood/RCC/PCC steel tubular /rail pole. | 20.00 | no | | 0.00 | INR Zero Only |
| 7 | Supplying and erection of 75mmX90 mm shackle insulator with G.I.Bolt.nuts and straps etc. as required . | 18.00 | no | | 0.00 | INR Zero Only |
| 8 | Supplying and erection of 100mmX80mm pin insulator complete with G. I.Spindle and nuts etc. as required. | 18.00 | Nos | | 0.00 | INR Zero Only |
| 9 | Erection of LV/MV shackle/Pin insulator etc as required | 38.00 | set | | 0.00 | INR Zero Only |
| 10 | Erection of all aluminium conductor of 7/3.40mm to 7/4.00mm diameter and above including binding etc. as required. | 159.00 | kg | | 0.00 | INR Zero Only |
| 11 | Erection of LED lights on pole/fabricated angle towers etc as and when required. | 20.00 | No | | 0.00 | INR Zero Only |
| 12 | Dismantling/recovery of LED/HPSV lights from steel tubular,Rail,joist, angle tower as and when required. | 15.00 | No | | 0.00 | INR Zero Only |
| 13 | Dismantling of over head lines comprising of copper/ aluminium over head conductor, Cl. wire, cross arms, insulators etc. as required. | 110.00 | kg | | 0.00 | INR Zero Only |
| 16 | Total impact of GST for the purpose of CTC | 1.000 | Nos | 0.00 | 0.00 | INR Zero Only |
| Total in Figures | | | | | 0.00 | INR Zero Only |

Quoted Rate in Words

INR Zero Only