

Item Rate BoQ

Tender Inviting Authority: Project Engineer(E&M), Bhurkunda Colliery, Barka-Sayal Area, CCL.							
Name of the Work / Contract No:		Gravel filling, Cable trench making and construction of transformer foundation at Main Substation under Bhurkunda Colliery.			NIT No. : PE(EnM)/BHK/e Tender/25-26/13 Dated: 04/07/2025		
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected)					
ITC Available	Works Contract	Bidder's Status (Mandatory)		Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select		0.00	0.00	0.00	
<p align="center">PRICE SCHEDULE</p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>							
NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	12	6	7	8
1	Supplying and installing following size of perforated painted with powder coating M.S. cable trays bends with perforation not more than 17.5%, joined with connectors, suspended from the ceiling with M.S. suspenders including bolts & nuts, painting suspenders etc as required. 600 mm width X 62.5 mm depth X 2.0 mm thickness	30.00	Each	INR		0.00	INR Zero Only
2	Excavation for cable trenches in soft soil, depth upto 1.2m including dressing of sides lift upto 1.5m, including getting out the excavated soil, refilling with sand and or good soil after laying of cable/ pipe etc in layers of 20 cm, ramming, watering and disposal of surplus excavated soil as directed, within a lead of 50 metres.	82.50	Mtrs	INR		0.00	INR Zero Only
3	Supplying, filling, spreading & leveling gravels of size range 5mm to 10mm, in there charge pit over the existing layer of boulders, in required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge.	160.00	Cum	INR		0.00	INR Zero Only
4	Laying of one number PVC insulated and PVC sheathed/XLPE power cable of 11 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. Above 120 sq. mm and upto 400 sq. mm	200.00	Mtrs	INR		0.00	INR Zero Only
5	Supplying and making outdoor cable end termination with heat shrinkable jointing kit complete with all accessories including lugs suitable for following size of 3 core, XLPE aluminium conductor cable of 11KV grade as required: 120 sq. mm	20.00	Each	INR		0.00	INR Zero Only
6	PCC 1:3:6 in Foundation (Plain cement concrete 1:3:6 nominal mix in foundation with crushed stone aggregate 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days.)	25.00	Cum	INR		0.00	INR Zero Only
7	Excavation in Soil by Manual Means. (Excavation for roadway in soil using manual means including loading in truck for carrying of cut earth to embankment site with all lifts and lead upto 1000 metres.) excluding Royalty but including, cost of watering, rolling & compaction	160.00	Cum	INR		0.00	INR Zero Only
8	Brick masonry work in 1:3 insub-structure complete excluding pointing and plastering, as per drawing and technical specifications	8.00	Cum	INR		0.00	INR Zero Only
9	Providing and Fixing of M.S Sheet 4mm	1,780.00	Kg	INR		0.00	INR Zero Only
10	Total impact of GST for the purpose of CTC	1.000	Nos	INR	0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					