

Validate

Print

Help

## Item Rate BoQ

Tender Inviting Authority: Staff officer (E&amp;M), NK Area, CCL

Name of the Work / Contract No:	Fabrication and erection of 15 Nos. Lighting Towers with fixing of flood light of different locations under NK Area			NIT No. GM (NK)/EnM/eNIT/2025-26/67; dated 04.07.2025.		
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00	
<b>PRICE SCHEDULE</b> (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc as required. Above 12.00 Metre and upto 16.00 Metre.	15.00	Nos		0.00	INR Zero Only
2	Supply and fixing of 50 mm x 50 mm x 6 mm angle for making hexagonal shape cross arm including cutting, welding, drilling holes, painting etc.	15.00	Set		0.00	INR Zero Only
3	Fixing of 08 nos. flood lights on lighting tower including connection cable etc as required (Lights to be supplied departmentally).	15.00	Set		0.00	INR Zero Only
4	Providing and fixing following capacity TP&N disconnecter fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc as required. 32 Amp TP&N	15.00	Each		0.00	INR Zero Only
5	Supply of 25 mm dia ISI marked, PVC conduit	675.00	Metre		0.00	INR Zero Only
6	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required 2 x 6 sq. mm	600.00	Each		0.00	INR Zero Only

7	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation and refilling the trench etc as required, but excluding sand cushioning and protecting covering. Up to 35 sq. mm	675.00	Metre		0.00	INR Zero Only
8	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				