

Tender Inviting Authority: Staff Officer (Civil),CCL, Giridih Area						
Name of Work:Beautification of Visarjan Talab at Akdoni Khurd village under CSR scheme of Giridih Area						
	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00	
<p align="center">PRICE SCHEDULE</p> <p align="center">(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</p>						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in charge. 2.6.1 All kinds of soil	5001.21	cum	128.05	640404.94	INR Six Lakh Forty Thousand Four Hundred & Four and Paise Ninety Four Only
2	Extraforeveryadditional lift of 1.5morpart thereof inexcavation/banking excavated or stacked materials. 2.26.1 All kinds of soil	120.00	cum	73.80	8856.00	INR Eight Thousand Eight Hundred & Fifty Six Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	11.42	Cum	5916.00	67560.72	INR Sixty Seven Thousand Five Hundred & Sixty and Paise Seventy Two Only
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6 (1 cement : 6 coarse sand)	25.88	cum	5322.15	137737.24	INR One Lakh Thirty Seven Thousand Seven Hundred & Thirty Seven and Paise Twenty Four Only
5	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand	37.36	sqm	284.75	10638.26	INR Ten Thousand Six Hundred & Thirty Eight and Paise Twenty Six Only
6	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	94.24	sqm	452.50	42643.60	INR Forty Two Thousand Six Hundred & Forty Three and Paise Sixty Only
7	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m. 2.28.1 All kinds of soil	251.25	sqm	19.75	4962.19	INR Four Thousand Nine Hundred & Sixty Two and Paise Nineteen Only
8	Dry stone pitching 22.5 cm thick including supply of stones and preparing surface complete	214.24	sqm	451.13	96650.09	INR Ninety Six Thousand Six Hundred & Fifty and Paise Nine Only
9	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	25.20	kg	92.55	2332.26	INR Two Thousand Three Hundred & Thirty Two and Paise Twenty Six Only

10	Lettering with black Japan paint of approved brand and manufacture	300.00	Per letter per cm height	3.70	1110.00	INR One Thousand One Hundred & Ten Only
11	Clearing grass and removal of the rubbish upto a distance of 50 m outside the periphery of the area cleared.	4374.00	sqm	5.20	22744.80	INR Twenty Two Thousand Seven Hundred & Forty Four and Paise Eighty Only
12	Filling available excavated earth (excluding rock) in trenches, plinth. sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50m and for all lift	158.58	cum	114.40	18141.55	INR Eighteen Thousand One Hundred & Forty One and Paise Fifty Five Only
13	CARRIAGE OF MATERIALS 1.1 By Mechanical Transport including loading, unloading and stacking Earth Lead - 5 km	965.03	cum	210.10	202752.80	INR Two Lakh Two Thousand Seven Hundred & Fifty Two and Paise Eighty Only
14	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					1256534.46	INR Twelve Lakh Fifty Six Thousand Five Hundred & Thirty Four and Paise Forty Six Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				