

Item Rate BoQ

Tender Inviting Authority: Project Engineer (Elect.), CHP-CPP, Piparwar Area							
Name of the Work / Contract No:		Installation of Sky-Net Type Lightning Arrestors at different Weighbridges and RFID Entry-Exit Gates under CHP-CPP, PPR.			NIT No. : PE(Elect.)e-NIT/25-26/10		
Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	
<div>PRICE SCHEDULE</div> <div>(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liaile to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)</div>							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (Excluding GST) in Rs. P	BASIC RATE In Figures To be entered by the Bidder (Without GST) in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	30	No	5,601.00		0.00	INR Zero Only
2	Providing and fixing 25 mm X 5 mm GI. strip on surface or in recess for connections etc. as required.	700	Mtr.	194		0.00	INR Zero Only
3	Providing and fixing 6 SWG dia GI. wire on surface or in recess for loop earthing as required.	1320	Mtr.	55		0.00	INR Zero Only
4	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - Exposed on wall 25 mm dia nominal bore.	100	Mtr.	403.20		0.00	INR Zero Only
5	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required.	6	No.	1875.00		0.00	INR Zero Only
6	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and secured with holding clamps, bolts, nuts, etc. as required.	18	No.	6508.00		0.00	INR Zero Only
7	Providing and fixing pole mount Lightening Arrestor.	36	No.	3034.35		0.00	INR Zero Only
8	pole painting	36	No.	1111.66		0.00	INR Zero Only
9	Providing and fixing bolts including nuts and washers complete. As per requirement.	1	Kg	111.65		0.00	INR Zero Only
10	Welding of strip for making Base plate on pole mount to fix the Lightning arrester.	918	CM	2.95		0.00	INR Zero Only
11	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					